

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB  
 (County)

LENOX TOWNSHIP  
 Located In: Corner Code #

1. Public Land Survey T 4 N R 14 E M-7  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R

3. Miscellaneous S T R  
 Property in Sec. S T R

SURVEY &  
 REMONUMENTATION

MAR 15 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, ROBERT H. BIRKETT, in a field survey on JULY 28, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 SEE BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 M-7 FOUND 5/8" BRASS ROD IN MONUMENT BOX AT THE CENTERLINE INTERSECTION OF COUNTY LINE ROAD (ASPHALT) AND 29 MILE ROAD, WEST (GRAVEL) AT A DEPTH OF 0.7'.

DISTANCES FROM M-7 LENOX TWP, MACOMB CNTY. TO A-7 CASCO TWP., ST CLAIR CNTY. (FND. 12.33')  
 3, 5) 12.33')

- 3, 4, 5) 56° 76.30' - DOUBLE HEAD NAIL W/ FLASHER IN SE FACE 32" OAK. (FND. 76.29')
- 3) 128° 42.61' - P.K. W/MCRC TAG IN NE FACE U.P. (FND. 42.67')
- 4, 5) 92.5' SW CENTER HYDRANT. (FND. 92.55')
- 4, 5) 52.8' NW CENTER PIPELINE MARKER. (FND. 52.7')
- 5) 42.6' SE SPIKE IN LIGHT POLE. (FND. 42.67')
- 5) 94.1' NNE SPIKE IN DEP (SW). (FND. 93.99')

FIELD MEASUREMENTS (SEE BACK)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-7 REPLACED 5/8" BRASS ROD IN EXISTING MONUMENT BOX WITH A 3/4" X 24" RE-BAR WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT, MI ACT 345, #41094, M-7".
- AZ. 0° - 12.33' - FOUND 1/2" IRON IN MONUMENT BOX A-7, CASCO TOWNSHIP, ST. CLAIR COUNTY, T. 14N., R. 15 E.
  - AZ. 10° - 93.99' - FOUND SPIKE IN WEST FACE UTILITY POLE.
  - AZ. 80° - 76.29' - FOUND P.K. NAIL WITH S.C.C.R.C. TAG IN SOUTHEAST ROOT 28" MAPLE.
  - AZ. 115° - 61.25' - FOUND P.K. NAIL WITH S.C.C.R.C. TAG IN WEST FACE 16" PINE.
  - AZ. 135° - 42.67' - FOUND P.K. NAIL WITH S.C.C.R.C. TAG BELOW SPIKE IN N.E. FACE UTILITY POLE WITH LIGHT
  - AZ. 190° - 92.55' - FOUND CENTER OF HYDRANT.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9/29/98  
 William E. Soderberg  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Robert H. Birkett Date 11-24-98  
 Surveyor's Michigan License No. 41094



SURVEY &  
REMONUMENTATION

A. Description of original monument and accessories and/or subsequent restoration:

MAR 15 1999

FROM FRONT

SECTION

1817 W. PRESTON, GLO, SET POST

- 1) 1977, ST. CLAIR COUNTY ROAD COM., FOUND P.K. NAIL, FIELD NOTES.
- 2) 1987, McNEELY LINCOLN, HAND HOLE NO POINT RECOVERED, UNRECORDED SURVEY.
- 3) 1993, UNKNOWN SOURCE, RECOVERED 3/4" BRASS ROD UNDER 0.5' ASPHALT, FIELD NOTES.
- 4) 1994, J. JAMES #19835, BRASS ROD IN HOLE CENTER PAVEMENT, UNRECORDED SURVEY.
- 5) 1995, ST. CLAIR COUNTY ROAD COM., BRASS ROD IN 4' DEEP HOLE, FIELD NOTES.
- 6) 1996, SPALDING, DeDECKER ASSOC., 1/2 BRASS ROD, CALCULATION SHEET.
- 7) 1997, McNEELY, LINCOLN, NOT STATED, FIELD NOTES AND CALCULATION SHEET.
- 8) 1998, METCO SURVEYING, NOT STATED, CALCULATION SHEET.

FIELD DISTANCES (FROM FRONT)

M-7 TO M-6, GLO (1817) - 40 CHAINS (2640')  
UNKNOWN SOURCE (1998) - 2698.50'  
RE-MONUMENTATION (1998) - 2698.35'

M-7 TO M-8, GLO (1817) - 40 CHAINS (2640')  
McNEELY, LINCOLN (1987) - 2676.13'  
JAMES (1994) - 2669.30'  
SDA (1996) - 2669.19'  
RE-MONUMENTATION (1998) - 2669.18'

M-7 TO A-7 CASE GLO 4.62'

C0863668 LIBER:08565 PAGE:914 09:45A 01/19/1999  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS