

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LENOX TOWNSHIP
 Located In: Corner Code #

MACOMB
 (County)

- | | | | |
|------------------------------------|-------|---------------------|------------|
| 1. Public Land Survey | | <u>T 4 N R 14 E</u> | <u>M-8</u> |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |

SURVEY &
 REMONUMENTATION

MAR 15 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT H. BIRKETT, in a field survey on JULY 28, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 SEE BACK
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 M-8 FOUND 1" BAR IN MONUMENT BOX CENTER OF COUNTY LINE ROAD, 1.2' DEEP.
 CORNER COMMON TO A-8 CASCO TOWNSHIP, T. 4 N., R. 15 E. ST. CLAIR COUNTY.

- NE - 110.75' (3) - PK WEST FACE UP. (FND. 110.60')
 EAST - 33.4' (4) - IRON #31596. (FND. 33.41')
 SE - 30.14' (1), 30.15' (2), 30.17' (3), 30.08' (5) - PK W/MCRC TAG SOUTH FACE DE POLE. (FND. 30.10')
 SE - 70.35' (2) - PK WEST FACE GTE SUPPORT POST. (FND. 70.45')
 SE - 29.9' (4) - SPIKE IN DE POLE. (FND. 29.81')
 WEST - 44.70' (1), 44.74' (3) - PK IN NORTH FACE DE POLE. (FND. 44.65'0)
 WEST - 60.00' (1), 60.00' (4) - CONCRETE MONUMENT. (FND. 59.95')
 WEST - 64.83' (5) - PK W/SCCRC TAG IN NORTH FACE 18" HICKORY. (FND. 64.85")
 NW - 89.80' - CENTER HYDRANT. (FND. 89.80')

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

FIELD DISTANCES - SEE BACK

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-8 REPLACED 1" IRON IN EXISTING MONUMNET BOX WITH A 3/4" X 24" RE-BAR WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT, MI ACT 345, #41094, M-8".

- AZ. 10° - 110.60' - FOUND P.K. NAIL WITH S.C.C.R.C. TSG IN WEST FACE TELEPHONE POLE.
 AZ. 105° - 30.10' - FOUND P.K. NAIL WITH MCRC TAG ABOVE SPIKE IN SOUTH FACE UTILITY POLR WITH TRANSFORMER.
 AZ. 270° - 59.95' - FOUND SQUARE CONCRETE MONUMENT WITH CAP #24608 IN NORTH-SOUTH FACE.
 AZ. 275° - 64.85' - FOUND P.K. NAIL WITH S.C.C.R.C. TAG IN NORTHEAST FACE 18" HICKORY.
 AZ. 300° - 81.45' - FOUND NAIL WITH CAP #37274 IN NORTHEAST FACE 28" MAPLE.
 AZ. 330° - 89.80' - FOUND CENTER NUT HYDRANT.



THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Robert H. Birkett Date 11-24-98
 Surveyor's Michigan License No. 41094

14 ✓
 820

SURVEY &
REMONUMENTATION

MAR 15 1999

SECTION

A. Description of original monument and accessories and/or subsequent restoration: FROM FRONT

- M-9 1817, W. PRESTON, GLO, SET POST
- 1) 1977, ST. CLAIR CO. ROAD COM., 5/8" BRASS PIN, FIELD NOTES.
 - 2) 1987, McNEELY, LINCOLN, 1" IRON IN MON. BOX, FIELD NOTES, UNRECORDED SURVEY.
 - 3) 1993, SPALDING, DeDECKER, 1" BAR IN MON. BOX, FIELD NOTES.
 - 4) 1995 THRU 1995, G. JAMES # 19835, MON. BOX, UNRECORDED SURVEYS.
 - 5) 1997, UNKNOWN, 1" IRON IN HAND HOLE, FIELD NOTES.
 - 6) 1996, SPALDING, DeDECKER, 1" BAR IN MON. BOX, CALCULATION SHEET.
 - 7) 1998, McNEELY, LINCOLN, UNKNOWN, CALCULATION SHEET.

FIELD DISTANCES - FROM FRONT

M-8 TO M-7 GLO(1817) - 40 CHAINS (2640)
McNEELY, LINCOLN (1987) - 2676.13'
JAMES (1994) - 2669.13'
SDA (1996) - 2669.19'
RE-MONUMENTATION (1998) - 2669.18'

M-8 TO M-9, GLO(1817) - 40 CHAINS (2640)
McNEELY, LINCOLN (1987) - 2697.61'
JAMES (1992) - 2697.75'
JAMES (1995) - 2697.66'
RE-MONUMENTATION (1998) - 2697.63'

C0863669 LIBER:08565 PAGE:916 09:45A 01/19/1999
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS