

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1091824
LIBER 9268 PAGE 12
12/27/1999 01:15:42 P.M.
MACOMB COUNTY, MI
CARMELLA SABAUGH, REG/DEEDS

For corners in

MACOMB
(County)

LENOX TOWNSHIP
Located In: Corner Code #

- | | | |
|------------------------------------|----------------------------|-------------|
| 1. Public Land Survey | T <u>4</u> N R <u>14</u> E | <u>M-11</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT H. BIRKETT, in a field survey on JULY 10, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:
M-11 LENOX. 1817 W. PRESTON, GLO, SET WOOD POST
(a) 1996, D. KING # 30085, 1/2" IRON WITH CAP # 15405, SURVEY, L. 7268, P. 956, M.C.R.
(b) 1991, ST. CLAIR COUNTY ROAD COMMISSION, 1" IRON IN MONUMENT BOX, L. 01, P. 195-196.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-11 LENOX. FOUND 1/2" IRON CENTER LINE COUNTY LINE ROAD @ PAVEMENT SURFACE.
S.S.W. - (a 78.19') NORTHEAST CORNER CONCRETE HEADWALL.

FIELD MEASUREMENTS
M-11 TO M-10 G.L.O. (1817) - 40 CHAINS (2640')
D. KING (1996) - 2724.86'
RE-MONUMENTATION (1999) - 2724.83'
M-11 TO M-12 G.L.O. (1817) - 40 CHAINS (2640')
RE-MONUMENTATION (1999) - 2712.86'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-11 LENOX. SET A 3/4" IRON WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT, M1 ACT 345, #41094, M-11" IN NEW MONUMENT BOX.

- AZ 0° 32.02' - FOUND 1" IRON IN MONUMENT BOX, A-11 T.4 N., R. 15 E., CASCO TOWNSHIP, ST. CLAIR COUNTY.
- AZ.35° 77.25' - FOUND NAIL WITH MDSH TAG IN SOUTH FACE UTILITY POLE.
- AZ.55° 69.00' - FOUND CHISELED X ON SOUTHWEST RIM MICHIGAN BELL MANHOLE. °
- AZ.110° 64.00' - FOUND NAIL WITH MDSH TAG IN SOUTH WEST FACE UTILITY POLE.
- AZ. 215° 79.87' - FOUND P.K. NAIL WITH ST. CLAIR COUNTY ROAD COMM. TAG IN NORTHWEST FACE LIGHT POLE.
- AZ. 255° 78.19' - NORTHEAST CORNER CONCRETE HEAD WALL.
- AZ. 295° 113.30' - FOUND NAIL WITH MDSH TAG IN NORTH FACE UTILITY POLE.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/5/99
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN



Signed by Robert H. Birkett Date November 23, 1999
Surveyor's Michigan License No. 41094