

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970.

For corners in

<u>Macomb</u> (County)	Located In: <u>Lenox</u>	Corner Code # <u>M-13</u>
1. Public Land Survey	T <u>4 N</u> R <u>14 E</u>	<u>M-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED IN MACOMB COUNTY
RECORDED AT: 8:30 A.M.

DEC 28 1993

Carroll A. Smith
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Steven E. Dunn, in a field survey on December 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
GLO Post - No. Evidence of Original Corner.
GLO Original survey performed by Preston 2-18-1818.

L.C.R.C.: (M.C.R.) L.2400, P.289 Herbert J. Kobs #14097 June 1, 1973
(S.C.C.R.) L.2, P. 76 & 77 George J. Avennt #16034 May 1, 1974

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
M-13 Found 1/2" Iron Rod in Monument Box. Corner Location agrees with Surveys in area.

Replaced with Macomb County Monument Marker #28408 on 3/4"x 24" Iron Rod.

ACCEPTED BY THE MACOMB COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
12-20-93

Frank J. Decker
FRANK J. DoDECKER, PS, PE, CHAIRMAN



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
M-13 T.4N.,R.14E.

Macomb County Monument Marker #28408 on 3/4"x 24" Iron Rod in Monument Box.

Witnesses:

- S.49°W. - 66.42' Found P.K. Nail on NW face of Utility Pole.
- N.44°W. - 67.75' Found P.K. Nail on SW face of Utility Pole.
- N.50°E. - 62.20' Found P.K. Nail on NW face of Utility Pole.
- S.38°E. - 57.35' Center top of Concrete R/W Marker.

The selected location is a careful and faithful perpetuation of the position of the original corner.

Signed by Steven E. Dunn Date 12-22-1993

Surveyor's Michigan License No. 28408