

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

C126173

94 SEP 30 AM 9:02

CARMEL A. SABAUGH
 REGISTER OF DEEDS
 MACOMB COUNTY, MI

For corners in

Macomb
 (County)

Located In: Bruce Township Corner Code #

- | | | | | | |
|------------------------------------|---|-----------|---|------------|-------------|
| 1. Public Land Survey | T | <u>5N</u> | R | <u>12E</u> | <u>A-13</u> |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | |
| | S | | T | | |
| 3. Miscellaneous Property in Sec. | S | | T | | |
| | S | | T | | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

LIBER 06464PG486

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on July 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Post was set common to Townships 4 & 5 North, Ranges 11 & 12 East
 12" White Oak S70°E 23 Links; 12" Black Oak N79°W 19 Links
- 1979-Verba, P.S. #13603; LCRC L.3074, Pg.5 - Fnd P.K. Nail
 - 1986-Avey, P.S. #15396; Survey L.05510, Pg.247 - Fnd P.K. Nail
 - 1993-Ward, P.S. #22445; Unrecorded LCRC - Fnd P.K. Nail (Addison Twp.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 5/8" x 24" Iron Rod w/2" diameter brass cap stamped "Oakland County Remonumentation, PS #22445" in a Monument Box in the centerline of 32 Mile Road, which has a bituminous surface, and centerline of Dequindre Road, which has a gravel surface.

Witnesses from LCRC #1, 2 & 3 were used to recover and verify the location of the found 5/8" x 24" Iron Rod w/2" diameter brass cap stamped "Oakland County Remonumentation", PS #22445 in a Monument Box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-28-94.
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 I found a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped "Oakland County Monument", PS #22445 in a Monument Box.
 N45°W 46.29' Fnd Chiseled "+" in top end of 24" C.M.P.
 S25°E 52.21' Fnd P.K. Nail & Oakland County Remonumentation Washer, P.S. #22445 in SW face Utility Pole
 N30°E 54.61' Fnd P.K. Nail & Oakland County Remonumentation Washer, P.S. #22445 in NW face Utility Pole
 N25°W 58.62' Fnd P.K. Nail & Oakland County Remonumentation Washer, P.S. #22445 in NE face Utility Pole
 S62°W 86.38' Fnd G.P.S. Monument #10012

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *Huston K. Kennedy* Date _____
 Surveyor's Michigan License No. 17623

