

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

APR 07 1998

For corners in

Macomb (County)	Located In: Bruce Township	Corner Code #
1. Public Land Survey	T 5N R 12E	B-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEE  
 GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN  
 PUBLIC ACT 345 OF 1990 AT A MEETING HE  
 ON JULY 10, 1997.

*William E. Soderberg*  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on 4/17, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post 12" White Oak S170°E 23 Links; 12" Black Oak N79°W 19 Links

- 1.) 1977-Kobs, PS #14097; LCRC L.2775, Pg.800 - Fnd 3/4" Iron Bar
- 2.) 1987-Kobs, PS #14097; LCRC L.4151, Pg.117 - Fnd 3/4" Iron
- 3.) 1976-Kobs, PS #14097; Survey L.2775, Pg.783 - Fnd 3/4" Iron Bar, used same wit as 1977 LCRC
- 4.) 1978-Kobs, PS #14097; Survey L.3021, Pg.144 - Fnd 3/4" Iron Bar, used same wit as 1977 LCRC
- 5.) 1980-Kobs, PS #14097; Survey L.3287, Pg.525 - Fnd 3/4" Iron Bar, used same wit as 1977 LCRC
- 6.) 1984-Kobs, PS #14097; Survey L.3705, Pg.126 - Fnd 3/4" Iron Bar, used same wit as 1977 LCRC
- 7.) 1986-Kobs, PS #14097; Survey L.3880, Pg.108 - Fnd 3/4" Iron Bar, used same wit as 1977 LCRC
- 8.) 1986-Kobs, PS #14097; Survey L.4077, Pg.588 - Fnd 3/4" Iron Bar, used same wit as 1977 LCRC
- 9.) 1987-Kobs, PS #14097; Survey L.4151, Pg.98 - Fnd 3/4" Iron Bar, used same wit as 1977 LCRC (over)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 3/4" Iron Rod 1.75 North of the existing centerline of 32 Mile Road extending to the East & West, which has a bituminous surface, 130 feet East of the approximate center of Stony Creek. Found a 1/2" Iron 101.74 feet to the East which is being used and accepted as the North 1/4 corner of Section 6, T4N, R12E, Washington Twp., (B-1).

Witnesses from LCRC #1, 2 & unrecorded Surveys #13, 14 & 15 were used to recover and verify the location of the found 3/4" Iron Rod.

Field measurements see back side of LCRC

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

B-13 I replaced the found 3/4" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped 345 #17623 in a new Monument Box  
 S71°W 65.99' Set PK & Remon Washer NW face Power Pole  
 N17°W 43.45' Set PK & Remon Washer West face 14" Ash  
 S67°E 86.80' Set PK & Remon Washer SW face Power Pole  
 N40°E 126.98' Set PK & Remon Washer SE face 17" Pine  
 East 101.74 Ft. North 1/4 corner of Section 6, T4N, R12E, Washington Twp., (B-1)



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *Huston Kennedy*  
 Surveyor's Michigan License No. 17623

Date 7-16-97

758

C0561139 LIBER:07589 PAGE:439 09:21A 08/13/1997  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

- 10.) 1987-Kobs, PS #14097; Survey L.4151, Pg.113 - Fnd 3/4" Iron Bar, used same wit as 1977 LCRC
- 11.) 1990-King, PS #30085; Survey L.4866, Pg.825 - Fnd 3/4" Iron Bar, used same wit as 1977 LCRC
- 12.) 1993-King, PS #30085; Survey L.5969, Pg.174 - Fnd 3/4" Iron Bar, used same wit as 1977 LCRC
- 13.) 1987-Avey, PS #15396; Unrecorded Survey - Fnd 1/2" Bar
- 14.) 1987-Avey, PS #15396; Unrecorded Survey - Fnd 1/2" Bar, used same wit as 1987 Unrecorded Survey
- 15.) 1992-Avey, PS #30076; Unrecorded Survey - Fnd 5/8" Bar

FIELD MEASUREMENTS BETWEEN

B-13 to A-13

GLO = 40 chains or 2640.00 Ft.  
Unrecorded survey by Herbert G. Avey, PS #15396 dated 8/12/87 = 2636.64 Ft.  
GRID-MEA = 2636.16 Ft.  
GROUND-MEA = 2636.61 Ft.

B-13 to B-1

No GLO  
GROUND-MEA = 101.74 Ft. (nea.)

B-13 to C-13

GLO = 40 chains or 2640.00 Ft.  
GRID-MEA = 2646.91 Ft.