

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
 REMONUMENTATION

APR 07 1998

For corners in

<u>Macomb</u> (County)	Located in: Bruce Township	Corner Code #
1. Public Land Survey	T 5N R 12E	F-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SECTION  
 ACCEPTED BY THE MACOMB COUNTY SURVEY  
 GROUP AS THE OFFICIAL CORNER UNDER MIC  
 PUBLIC ACT 345 OF 1990 AT A MEETING  
 ON JULY 10, 1997  
*William E. Soderberg*  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Huston K. Kennedy, in a field survey on 5/8, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 16" Birch N16°E 18 Links; 16" Birch S82°W 33 Links
- 1.) 1974 "CEDAR VIEW SUBDIVISION", L.66, Pgs. 10-12
- 2.) 1976-Kobs, PS #14097; LCRC L.2681, Pg.137 - Fnd 1/2" Iron Bar
- 3.) 1980-Fenn, PS #23505; LCRC L.3205, Pg.648 - Fnd 1/2" Rod
- 4.) 1984-Kobs, PS #14097; Survey L.3380, Pg.66 - Fnd 1/2" Iron Bar, used the same wit as 1980 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod .50 feet below the surface and 1.32 feet South of the existi centerline of 32 Mile Road extending to the East & West, which has a bituminous surface. A fence-plat line extending to the Nort Found a 1/2" Iron Rod that is being used and accepted as the North 1/4 corner of Section 4, T4N, R12E, Washington Township (F- is located 359.96 feet to the East.

Witnesses from LCRC #1, 2 and "CEDAR VIEW SUBDIVISION" were used to recover and verify the location of the found 1/2" Iron Ro

See back side of LCRC for Field Measurements

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County #17623 in a new Monument Box  
 S41°W 34.01' Set PK & Remon Washer NW face Power Pole  
 S46°E 84.20' Set PK & Remon Washer SW face 11" Elm  
 N47°E 77.28' Set PK & Remon Washer SE face Power Pole  
 N71°E 133.05' Set PK & Remon Washer SE face 29" Oak  
 East 360.11 feet, North 1/4 corner of Section 4, T4N, R12E, Washington Twp. (F-1)



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of t position of the original corner.

Signed by *Huston K. Kennedy*  
 Surveyor's Michigan License No. 17623

Date 7-16-97

7102

C0561135 LIBER:07589 PAGE:431 09:21A 08/13/1997  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

FIELD MEASUREMENTS BETWEEN

F-13 to E-13

No GLO

Unrecorded survey by Fenn & Associates dated 5/2/97 = 2643.63 Ft.  
Calculated = 2642.56 Ft.

F-13 to F-1

No GLO

GRID-WEA = 360.11 Ft.

F-13 to G-13

GLO = 40 chains or 2640.00 Ft.  
GRID-WEA 2971.12 Ft.