

SURVEY &  
REMONUMENTATION

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb

(County)

Located in Bruce Township Corner Code #

1. Public Land Survey	T	5N	R	12E	G-12
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PE  
GROUP AS THE OFFICIAL CORNER UNDER MICHIG  
PUBLIC ACT 345 OF 1990 AT A MEETING HE  
ON 8/5/97

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on 7/2, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:  
1817-GLO Wampler, D.S.; Set Post 16" White Oak N80°E 10 Links; 21" Red Oak S53°W 25 Links  
1.) 1972-Kobs, PS #14097; LCRC L.2332, Pg.293 - Fnd 1" Pipe  
2.) 1979-Avey, PS #15396; LCRC L.3173, Pg.576 - Fnd 1" Pipe  
3.) 1972-Kobs, PS #14097; Survey L.2334, Pg.261 - Fnd 1" Pipe, used same wit as 1972 LCRC  
4.) 1974-Kobs, PS #14097; Survey L.2534, Pg.459 - Fnd 1" Pipe, used same wit as 1972 LCRC  
5.) 1976-Kobs, PS #14097; Survey L.2681, Pg.131 - Fnd 1" Pipe, used same wit as 1972 LCRC  
6.) 1976-Kobs, PS #14097; Survey L.2723, Pg.869 - Fnd 1" Pipe, used same wit as 1972 LCRC  
7.) 1977-Kobs, PS #14097; Survey L.2788, Pg.386 - Fnd 1" Pipe, used same wit as 1972 LCRC

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron inside a 1" Iron Pipe 6" below the surface, 2 feet East of the existing centerline of Campground Road extending to the North & South, which has a gravel surface, and in the existing centerline of Gates Road extending to the West, which has a gravel surface, and bituminous surface extending to the East.

Witnesses from LCRC #1, 2 and Survey #7 were used to recover and verify the location of the found 1/2" Iron inside a 1" Iron Pipe.

See back side of LCRC for Field Measurements

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 I replaced the found 1/2" Iron inside a 1" Iron Pipe with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped Macomb County Monument MI Act 345 #17623  
N72°W 103.40' Set PK & Remon Washer South face 26" Oak  
N37°W 96.26' Set PK & Remon Washer SW face 27" Oak  
N44°E 43.97' Set PK & Remon Washer NE face Guide Pole  
S61°E 80.20' Set PK & Remon Washer NE face 26" Willow

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *Huston K. Kennedy*  
Surveyor's Michigan License No. 17623

Date 8-8-97



7123

FIELD MEASUREMENTS BETWEEN

G-12 to G-11

GLO = 40 chains or 2640.00 Ft.

Survey, Liber 2534, Page 459 (5/14/74) = 2712.43 Ft. (Section 34)

G-12 to G-13

GLO = 40 chains or 2640.00 Ft.

Survey Liber 2681, Page 131 (2/16/76) = 2640.26 Ft. (Section 33)

"SUPERVISOR'S PLAT OF MOUNTAIN VIEW ORCHARD FARMS" = 2641.00 Ft. (Section 34)

GROUND-MEA = 2640.61 Ft.

GRID-MEA = 2640.06 Ft. or GROUND CAL. = 2640.30 Ft.

C0568791 LIBER:07613 PAGE:805 10:28A 09/02/1997  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS