

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

For corners in

<u>Macomb</u> (County)	Located In: Bruce Township	Corner Code #
1. Public Land Survey	T <u>5N</u> R <u>12E</u>	<u>G-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on 4/1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

1817-GLO Wampler, D.S.; Set Post 12" White Oak N07°W 60 Links

1.) 1976-Kobs, PS #14097; L.2681, Pg.137 - Fnd 3/8" Pipe

2.) 1976-Kobs, PS #14097; L.2681, Pg.131 - Fnd 3/8" Iron Pipe, used same wit as 1976 LCRC

3.) 1986-King, PS #30085; L.4077, Pg.588 - Fnd 3/8" Iron Pipe, used same wit as 1976 LCRC

4.) 1988-King, PS #30085; L.4375, Pg.850 - Fnd 3/8" Iron Pipe, used same wit as 1976 LCRC

ACCEPTED BY THE MACOMB COUNTY SURVEY GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING ON 8/5/97

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner has since been perpetuated with a empty Monument Box 2.40 feet North of the existing centerline of 32 Mile Road extending to the East & West, which has a bituminous surface and in the existing centerline of Campground Road extending to the North, which has a gravel surface, and 56 feet West of the existing centerline of Campground Road extending to the South, which has a bituminous surface. I found a P.K. Nail 55.58 feet to the East, which is being used and accepted as a common corner to Sections 3 & 4, T4N, R12E, Washington Twp. (G-1).

Witnesses from LCRC #1 were used to recover and verify the location of the found empty Monument Box.

See back side of LCRC for Field Measurements

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623 in the existing Monument Box

N45°E 57.02' Set PK & Remon Washer SE face Guide Pole

N44°W 53.45' Set PK & Remon Washer SW face Power Pole

S23°E 30.42' Set PK & Remon Washer NE face Power Pole

S66°E 88.60' Set PK & Remon Washer NE face Power Pole

East 55.58 feet, corner common to Sections 3 & 4, T4N, R12E, Washington Twp., (G-1)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available position of the original corner.

Signed by [Signature]
 Surveyor's Michigan License No. 17623

Date 8-8-97



FIELD MEASUREMENTS BETWEEN

F-1 to G-13

No GLO

Survey dated 2/18/76, Liber 2681, Pg. 131 = 2680.61 Ft.

GPS-MEA = 2611.20 Ft. or GROUND CAL. = 2611.44 Ft.

G-13 to F-13

GLO = 40 chains or 2640.00 Ft.

GPS-MEA = 2971.31 Ft. or GROUND CAL. = 2971.58 Ft.

G-13 to G-1

GLO = 80 links or 52.80 Ft.

GPS-MEA = 55.57 Ft. or GROUND CAL. = 55.58 Ft.

G-13 to H-13

GLO = 40 chains or 2640.00 Ft.

GPS-MEA = 2678.23 Ft. or GROUND CAL. = 2678.47 Ft.

C0568792 LIBER:07613 PAGE:807 10:28A 09/02/1997
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS