

APR 29 1998

COMM

C0283929 LIBER:06842 PAGE:100 01:43P 12/07/1995
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Macomb

(County)

Located In: Bruce Twp. Corner Code #

- 1. Public Land Survey T 5N R 12E H-9
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, Huston K. Kennedy, in a field survey on November 10, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey Instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 18" Sassafras N30°E 28 Links; 8" White Oak S63°W 48 Links
- 1.) 1971-Kobs, PS #14097; LCRC L.2225, Pg.72 - Fnd 1/2" Iron Bar w/cap #14097
- 2.) 1990-Kobs, PS #14097; LCRC L.4866, Pg.801 - Fnd 1/2" Iron Rod
- 3.) 1971-Kobs, PS #14097; Survey L.2225, Pg.57 - Fnd 1/2" Iron Rod
- 4.) 1971-Kobs, PS #14097; Survey L.2225, Pg.58 - Fnd 1/2" Iron Rod, used same wit as Survey #3
- 5.) 1979-Kobs, PS #14097; Survey L.3126, Pg.128 - Fnd 1/2" Iron Rod, used same wit as Survey #3
- 6.) 1980-Kobs, PS #14097; Survey L.3287, Pg.553 - Fnd 1/2" Iron Rod, used same wit as Survey #3
- 7.) 1983-Kobs, PS #14097; Survey L.3466, Pg.307 - Fnd 1/2" Iron Bar
- 8.) 1984-Kobs, PS #14097; Survey L.3579, Pg.120 - Fnd 1/2" Iron Bar, used same wit as Survey #7
- 9.) 1985-King, PS #30085; Survey L.3880, Pg.102 - Fnd 1/2" Iron Bar

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron 2 feet South of the centerline of 34 Mile Road, which has a gravel surface extending to the East & West and is 15 feet West of a branch of the East Pond Creek Crossing, and 60 feet West of the centerline of the driveway for house #11000.

Witnesses from LCRC #2 were used to recover and verify the location of the found 1/2" Iron.

FIELD MEASUREMENTS BETWEEN

H-9 to G-9 2677.34 Ft., GLO = 40.42 chains or 2667.72 Ft.
G-9 to I-9 2643.04 Ft., GLO = 40.42 chains or 2667.72 Ft.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-1-95

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-9 I replaced the found 1/2" Iron with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623"
- N22°W 92.75' Set PK & Remon. Washer SW face 13" Elm
- Due South 31.20' Set PK & Remon. Washer East face Power Pole
- S47°E 71.20' NW corner of the East stone driveway pillar
- S63°E 90.37' Set PK & Remon. Washer NE face 10" Pine

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Dustin K. Kay
Surveyor's Michigan License No. 17623

Date December 4, 1995

