

APR 29 1996

C0283930 LIBER:06842 PAGE:101 01:43P 12/07/1995 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb (County)

Located In: Bruce Twp. Corner Code #

- 1. Public Land Survey T 5N R 12E H-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at row 11, column H.

I, Huston K. Kennedy, in a field survey on November 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 14" White Oak N39°E 10 Links; 13" White Oak S73°W 23 Links
1.) 1976-Kobs, PS #14097; LCRC L.2747, Pg.933 - Fnd 1" Iron Pipe
2.) 1995-King, PS #30085; LCRC L.6586, Pg.189 - Fnd 1/2" Iron
3.) 1976-Kobs, PS #14097; Survey L.2747, Pg.925 - Fnd 1" Pipe
4.) 1979-Kobs, PS #14097; Survey L.3074, Pg.503 - Fnd 1" Pipe, used same wit as 1976 Survey
5.) 1982-Kobs, PS #14097; Survey L.3421, Pg.552 - Fnd 1" Pipe, used same wit as 1976 Survey
6.) 1982-Kobs, PS #14097; Survey L.3421, Pg.554 - Fnd 1" Pipe, used same wit as 1976 Survey
7.) 1982-Kobs, PS #14097; Survey L.3421, Pg.556 - Fnd 1" Pipe, used same wit as 1976 Survey
8.) 1984-Kobs, PS #14097; Survey L.3579, Pg.123 - Fnd 1/2" Iron Bar
9.) 1984-Kobs, PS #14097; Survey L.3705, Pg.131 - Fnd 1" Pipe, used same wit as 1976 Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod 4 feet South of the center of 33 Mile Road, which has a gravel surface extending to the East & West, and 62 feet East of the center of Romeo Orchard Street, which has a bituminous surface. I also found a second 1/2" Iron Rod w/cap PS #30085 9.75 feet to the West.

Witnesses from LCRC #2 and Surveys #3-9 were used to recover and verify the location of the found 1/2" Iron Rod which I did not accept. I accepted the found 1/2" Iron Rod to the East for the following reasons listed on the back of this LCRC.

FIELD MEASUREMENTS BETWEEN

- H-11 to G-11 2673.43 Ft., (m), GLO = 40.40 chains or 2666.40 Ft.
2663.69 Ft. (Liber 3074, Pg.503)
H-11 to I-11 2653.90 Ft. (Plat)
2654.76 Ft. (MCS)
2654.75 Ft. (m), GLO = 40.40 chains or 2666.40 Ft.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-2-95

Signature of William E. Soderberg, WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-11 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623"
N03°E 45.36' Set PK & Remon. Washer West face 24" Poplar North 59.75 Ft. Found 1/2" Iron Rod
S40°W 46.40' Set PK & Remon. Washer SE face Power Pole South 50.02 Ft. Found 1/2" Iron Pipe
S37°E 89.43' Set PK & Remon. Washer NE face 13" Maple West 9.75 Ft. Found 1/2" Iron Rod w/cap PS #30085
S77°E 162.17' Set PK & Remon. Washer North face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence for the position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date December 4, 1995