

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb
 (County)

Located In: Bruce Twp Corner Code #

**SURVEY &
 RE-MONUMENTATION**

FEB 27 1997

COMMISSION

1. Public Land Survey	T <u>5</u> N R <u>12</u> E	<u>I-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34	●	35		36	
13													

I, Huston K. Kennedy, in a field survey on 4/12, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 16" White Oak S37°E 20 Links; 17" White Oak N50°W 34 Links
 1.) 1977-Hooth, PS #7966; LCRC L.2891, Pg.389 - Fnd 1/2" Rod in a Monument Box
 2.) 1990-Kobs, PS #14097; LCRC L.4997, Pg.958 - Fnd 1/2" Iron Bar in a Monument Box

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-21-96
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod in a Monument Box 4 feet South of the existing centerline of Gates Road extending to the East & West, which has a bituminous surface, and 22 feet East of the driveway for house #11591.


Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 1/2" Iron Rod in a Monument Box.

FIELD MEASUREMENTS BETWEEN
 I-12 to I-13 GLO = 40 chains or 2640.00 Ft., 2712.08 Ft. (GPS-MEA)
 I-12 to I-11 GLO = 40 chains or 2640.00 Ft., 2632.82 Ft. (GPS-MEA)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 I-12 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623 in a existing Monument Box
 S40°W 68.15' Set PK & Remon Washer North face 42" Oak
 Due South 30.26' Set PK & Remon Washer East face 44" Oak
 S40°E 50.28' Set PK & Remon Washer East face 40" Oak
 N55°E 39.21' Set PK & Remon Washer East face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
 Surveyor's Michigan License No. 17623

Date 12-12-96


620