

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &
REMONUMENTATION**

For corners in

Macomb
(County)

Located in: Bruce Twp Corner Code # _____

FEB 27 1997

COMMISSION

- | | | |
|------------------------------------|----------------------------|-------------|
| 1. Public Land Survey | T <u>5</u> N R <u>12</u> E | <u>I-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on 5/3, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set Post 18" White Oak N73°W 1.42 Chains; 8" White Oak S13°W 1.26 Chains
No Land Corner Recordation Certificates or Recorded Certificates of Survey were found for this corner.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-21-96
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner was recovered by using "ASSESSOR'S PLAT No. 2" recorded in Liber 17 of Plats, on page 22 of Macomb County Records. I found a concrete monument at the Southwest corner of Lot 22, Northwest corner of Lot 20 and the Northeast corner of Lot 21: I also found an Iron Rod at the Southwest corner of Lot 28. The relationship between the recorded and measured angular and distance were very close. I set temporary corner (I-13) 33.00 feet from the Southwest corner of Lot 22 and plunged from the Northwest corner of Lot 20. The corner common to Section 2 & 3, T4N, R12E, Washington Township (I-1) is located 7.22 feet to the East. The GLO stagger is 11 links or 7.26 feet.

FIELD MEASUREMENTS BETWEEN
I-13 to I-12 GLO = 40 chains or 2640.00 Ft., 2712.08 (GPS-MEA)
I-13 to J-13 GLO = 40 chains or 2640.00 Ft. & 2662.16 Ft. (GPS-MEA)
I-13 to J-1 GLO = 11 links or 7.26 Ft. & 7.22 Ft. (MEA)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I-13 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623 in a new Monument Box.
N01°W 34.91' Set PK & Remon Washer East face Power Pole
N64°E 59.04' Set PK & Remon Washer SE face 18" Maple
S58°E 60.49' Set PK & Remon Washer NE face 25" Maple
S60°W 46.65' Set PK & Remon Washer NW face Power Pole
East 7.22 feet corner common to Sections 2 & 3, T4N, R12E, Washington Twp., (I-1)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date 12-12-96

