

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

**SURVEY &  
REMONUMENTATION**

For corners in

Macomb  
(County)

Located in Bruce Twp Corner Code #

FEB 27 1997

COMMISSION

1. Public Land Survey	T <u>5N</u> R <u>12E</u>	<u>J-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Huston K. Kennedy, in a field survey on 4/12, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
1817-GLO Wampler, D.S.; Set Post 24" White Oak N21°E 11 Links; 24" Elm S53°W 7 Links  
1.) 1980-Miller, PS #13589; LCRC L.3288, Pg.637 - Fnd Disc on Copperclad Rod  
2.) 1992-Dunn, PS #28408; LCRC L.5347, Pg.565 - Fnd Disc on Copper Rod

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 4-16-96  
William E. Soderberg  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd Copper Clad 1/2" Iron Rod 0.5 feet South of the existing centerline of 32 Mile Road extending to the East & West, which has a bituminous surface. North 1/4 corner of Section 2, T4N, R12E, Washington Twp., was recovered 14.06 feet to the East.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found Copper Clad 1/2" Iron Rod.

FIELD MEASUREMENTS BETWEEN

J-13 to I-13 GLO = 40 chains or 2640.00 Ft., 2262.16 Ft. (GPS-MEA)  
J-13 to J-1 No GLO, 14.06 Ft., (MEA) and 13.96 Ft. L.3288, Pg.637  
J-13 to K-13 GLO = 40 chains or 2640.00 Ft., 2657.00 Ft. (GPS-MEA)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 I replaced the found Copper Clad 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623 in a new Monument Box  
S12°E 27.41' Set PK & Remon Washer West face Power Pole  
S46°W 48.94' Set PK & Remon Washer NW face 14" Maple  
S74°E 91.94' Top Bolt on Fire Hydrant  
N55°E 55.74' Set PK & Remon Washer SW face 16" Maple  
East 14.06 feet North 1/4 corner Section 2, T4N, R12E, Washington Twp., (J-1)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available position of the original corner.

Signed by [Signature]  
Surveyor's Michigan License No. 17623

Date 12-12-96



6022