

**SURVEY & REMONUMENTATION**

APR 29 1996

**COMMISSION**

C0283936 LIBER:06842 PAGE:107 01:43P 12/07/1995  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Macomb (County) Located In: Bruce Twp. Corner Code # \_\_\_\_\_

- 1. Public Land Survey T 5N R 12E K-10  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy in a field survey on November 10, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
1817-GLO Wampler, D.S.; Set Post 7" Birch S20°E 4 Links; 20" Black Oak N11°E 24 Links  
1.) 1974-Kobs, PS #14097; LCRC L.2549, Pg.13 - Fnd PK Nail & reset w/1/2" Iron Bar  
2.) 1974-Kobs, PS #14097; Survey L.2548, Pg.964 - Fnd 1/2" Iron Bar, used same wit as 1974 LCRC

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1995 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron in a Monument Box 4 feet West of the centerline of McKay Road, which has a bituminous surface extending to the North & South. A tree-fence row extending to the East & West, and 156 feet South of the driveway for house #72045.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron in a Monument Box.

**FIELD MEASUREMENTS BETWEEN**

K-10 to K-9 2665.48 Ft., GLO = 40 chains or 2640.00 Ft.  
K-10 to K-11 2428.22 Ft., GLO = 40 chains or 2640.00 Ft.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-1-95  
*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
K-10 I replaced the found 1/2" Iron with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.  
N86°E 35.70' Set PK & Remon. Washer North face Power Pole  
N37°E 70.42' Set PK & Remon. Washer NW face 10" triple Ash  
N23°E 143.43' Set PK & Remon. Washer West face 27" Maple  
N88°W 31.52' Set PK & Remon. Washer North face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by *Huston K. Kennedy*  
Surveyor's Michigan License No. 17623

Date December 4, 1995