

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

SURVEY &  
 REMON

For corners in

Macomb

(County)

Located In: Bruce Twp Corner Code #

FEB 27 1997

COMMISS

1. Public Land Survey	T <u>5</u> N R <u>12</u> E	<u>K-12</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Huston K. Kennedy, in a field survey on 4/12/96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 16" White Oak S37°E 20 Links; 17" White Oak N50°W 34 Links  
 1.) 1980-Miller, PS #13589; LCRC L.3288, Pg.638 - Fnd Concrete Monument with 3/4" Iron Rod  
 2.) 1986-Kobs, PS #14097; LCRC L.4077, Pg.540 - Fnd Concrete Monument  
 3.) 1986-Kobs, PS #14097; Survey L.4077, Pg.564 - Fnd Concrete Monument, used same wit as 1986 LCRC  
 4.) 1987-Kobs, PS #14097; Survey L.4543, Pg.88 - Fnd Concrete Monument, used same wit as 1986 LCRC

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-21-96

*William E. Soderberg*  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd Concrete Monument with a 3/4" Iron Rod and a tree, rock & fence row extending to the North & South with a tree row extending to the West.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found Concrete Monument with a 3/4" Iron Rod.

FIELD MEASUREMENTS BETWEEN

K-12 to J-12\* 2640.22 Ft., L.4077, Pg.564, L.4543, Pg.88, 2640.50 Ft. M.D.O.T.  
 K-12 to K-11 GLO = 40 chains or 2640.00 Ft., 2815.69 Ft. (GPS-MEA)  
 K-12 to K-13 GLO = 40 chains or 2640.00 Ft., 2636.38 Ft. M.DOT, 2636.46 Ft. (GPS-MEA 1996)

\*The unapproved position of the Center Post

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 I placed 2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623 on a existing Concrete Monument  
 Due West 8.75' Set PK & Remon Washer South face 10" Elm  
 S34°W 15.40' Set PK & Remon Washer SE face 9" Oak  
 S05°E 18.61' Set PK & Remon Washer West face 12" Ash  
 S85°E 18.76' Set PK & Remon Washer North face 23" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by *Huston Kennedy*  
 Surveyor's Michigan License No. 17623

Date 12-12-96

623