

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Macomb

(County)

Located In: Bruce Twp Corner Code #

**SURVEY &  
 REMONUMENTATION**

FEB 27 1997

COMMISSION

Register of Deeds Stamp & File Number

1. Public Land Survey	T <u>5</u> N	R <u>12</u> E	<u>K-13</u>
	T <u>   </u>	R <u>   </u>	<u>   </u>
	T <u>   </u>	R <u>   </u>	<u>   </u>
	T <u>   </u>	R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u>	T <u>   </u>	R <u>   </u>
	S <u>   </u>	T <u>   </u>	R <u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u>	T <u>   </u>	R <u>   </u>
	S <u>   </u>	T <u>   </u>	R <u>   </u>

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Huston K. Kennedy, in a field survey on 6/3, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:  
 1817-GLO Wampler, D.S.; Set Post 18" Beech N09°E 54 Links; 18" Beech S18°W 32 Links  
 1.) 1980-Miller, PS #13589; LCRC L.3288, Pg.639 - Fnd 1" Pipe  
 2.) Unrecorded Macomb County Road Commission Witnesses - Fnd 3/4" Iron Pipe

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-9-96  
William E. Soderberg  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1996 Kennedy Surveying, Inc. - Kennedy, PS #17623 - 1" Iron Pipe in the existing centerline of 32 Mile Road extending to the East & West, which has a bituminous surface with a tree-fence row extending to the North. Corner common to Sections 1 & 2, T4N, R12E, Washington Twp., (K-1) is located 42.87 feet to the East. The existing conditions are based upon a LCRC recorded in Liber 3288, Page 639. Due to the construction and widening of M-53 and 32 Mile Road intersection, all the witnesses were destroyed and the corner was not reset. (Over)

FIELD MEASUREMENTS BETWEEN

K-13 to J-13 GLO = 40 chains or 2640.00 Ft., 2657.00 Ft. (GPS-MEA) and 2657.15 Ft. (M.DOT)
K-13 to K-1 GLO = 1.24 chains or 81.84 Ft., 42.87 Ft. (MEA) and 42.86 Ft. L.3288, Pg.639
K-13 to K-12 GLO = 40 chains or 2640.00 Ft., 2636.46 Ft. (GPS-MEA) and 2636.38 Ft. (M.DOT)
K-13 to L-13 GLO = 40 chains or 2640.00 Ft., 2790.88 Ft. (GPS-MEA 1996)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 K-13 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623 in a new Monument Box.  
 N55°E 110.26' Set PK & Remon Washer NW face 12" Maple  
 N70°W 47.79' Set PK & Remon Washer SW face Guide Pole  
 S56°W 41.14' Set PK & Remon Washer NW face Power Pole  
 S52°E 101.52' Set PK & Remon Washer NE face Power Pole  
 East 42.87 feet East corner common to Sections 1 & 2, T4N, R12E, Washington Twp., (K-1) 5/8" Iron Rod

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]  
 Surveyor's Michigan License No. 17623

Date 12-12-96  


6024