

SURVEY &
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APR 07 1998

For corners in

<u>Macomb</u> (County)	Located In: <u>Bruce Township</u>	Corner Code # <u>L-11</u>
1. Public Land Survey	T <u>5N</u> R <u>12E</u>	<u>L-11</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990 AT A MEETING HELD
ON 8/5/97

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	13		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Huston K. Kennedy, in a field survey on 8/1, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set Post 18" Beech N01°W 14 Links; 8" Beech S86°W 26 Links
1.) 1978-Kobs, PS #14097; LCRC L.2923, Pg.869 - Fnd 1/2" Iron Pipe.
2.) 1985-Kennedy, PS #17623; Unrecorded Survey - Fnd 3/4" Iron Pipe.
3.) 1942-Lehner RLS; Unrecorded witnesses - Object found not stated

C0585105 LIBER:07661 PAGE:1 09:11A 10/01/1997
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd capped 1/2" Iron Rod 5" below the surface in the existing centerline of 3 Mile Road extending to the East & West, which has a gravel surface. Found a second 1/2" Iron Pipe 5.47 feet to the West. There is no line of occupation to the North or South.

Witnesses from unrecorded witnesses #3 were used to recover and verify the location of the found capped 1/2" Iron Rod.

See back side of LCRC for Field Measurements

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 I replaced the found 1/2" capped Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "HUSTON KENNEDY MONUMENT MI Act 345" #17623
N35°W 65.18' SE corner of house #14381
N18°E 42.70' Set PK & Remon Washer West face Guide Pole
S31°W 86.43' NW corner of house #14380
S06°W 27.24' Set PK & Remon Washer East face Power Pole
West 5.47 feet, found 1/2" Iron Pipe

S05°W 33.03 feet found 1/2" Iron Rod

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *H. Kennedy*
Surveyor's Michigan License No. 17623

Date 8-29-97



g+w

7166

FIELD MEASUREMENTS BETWEEN

L-11 to K-11

GLO = 39.84 chains or 2629.44 Ft.

M.C.P.C. Map I-S = 2603.35 Ft.

GROUND-MEA = 2808.34 Ft.

GRID-MEA = 2608.69 Ft. or GROUND CAL. = 2608.93 Ft.

L-11 to M-11

GLO = 39.84 chains or 2629.44 Ft.

H.C.P.C. Map I-S = 2635.73 Ft.

GROUND-MEA = 2629.43 Ft.

Survey recorded in Liber 2923, page 829 = 2629.36 Ft.

GRID-MEA = 2628.96 Ft. or GROUND CAL. = 2629.21 Ft.

C0585105 LIBER:07661 PAGE:2 09:11A 10/01/1997
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS