

LIBER 06166P0063

R999676

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 RECORDED IN MACOMB COUNTY

RECORDS AT: 8:30 AM

For corners in

MACOMB (County)

Located In: Bruce Township Corner Code # M-1

DEC 28 1993

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 5N R 12E M-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

I, Shelby W. Money, in a field survey on November 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

POST G.L.O. NOTES / PAGES 525 AND 527
LCRC (1973) LIBER 2400 PAGE 287 MACOMB COUNTY, BRUCE TOWNSHIP / T.RN., R.12E.
PER G.L.O. NOTES: CORNER IN COMMON TO T.5 & 6N., R.12 & 13E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/8" REBAR
FOUND WITNESS FROM L.C.R.C. / MACOMB COUNTY
NORTHEAST 16" MAPLE TREE 60.05' NO NAIL
FOUND 3/8" IRON SOUTH
OLD FENCE LINE NORTH TO QUARTER CORNER
WEST 2.0'+ CENTERLINE 36" CMP END 10' SOUTH AND 20' NORTH
NORTH 5.0'+ CENTERLINE GRAVEL ROAD

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93
FRANK J. DECKER, P.S., PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET LAPEER COUNTY REMONUMENTATION MARKER #30092 / M-13 OVER 3/8" REBAR
N 15° E 34.53' LAPEER TAG IN WEST FACE OF 18" ASH TREE
N 60° E 59.82' LAPEER TAG IN SOUTHEAST FACE 10" MAPLE TREE
S 80° E 190.60' LAPEER TAG IN NORTH FACE OF 24" MAPLE TREE
S 10° E 27.23' LAPEER TAG IN WEST FACE 8" OAK TREE
SOUTH 33.00' 1/2" REBAR



Signed by Shelby W. Money
Surveyor's Michigan License No. 30092

Date 12-15-93