

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &  
 REMONUMENTATION**

For corners in

<u>Macomb</u> (County)	Located in: Bruce Township	Corner Code # M-3
1. Public Land Survey	T <u>5N</u> R <u>12E</u>	<u>M-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

MAR 17 2000

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 7-27-99

*William E. Soderberg*  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on April 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- A. Description of original monument and accessories and/or subsequent restoration:  
 1817-GLO Wampler, D.S.; Set Post 12" Sugar Tree East 5 Links; 14" Maple N49°W 14 Links
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - After a lengthy discussion with the peer group, the corner was recovered on a line between A-3 T5N, R13E, M-4 T5N, R12E, and at the distance shown 2515.51 feet as shown on the M.C.P.C. Map for Bruce Township (1-F) which puts this corner 0.18 feet South of A-3 (Armada Twp.) This position was adjusted 0.18 feet to the North and resulting in a common corner with A-3 (Armada Township). The corner as recovered is located 10 feet West of a existing ditch extending to the North & South. There are no lines of occupation to the East or West.

**FIELD MEASUREMENTS BETWEEN**

**M-3 to A-3**  
 GLO = 30 Links or 19.80 Ft.  
 M-3 (Bruce Township) as recovered, is a common corner to A-3

**M-3 to M-4**  
 GLO = 40 chains or 2640.00 FT  
 2515.51 Ft. (MCPC Map)  
 2515.69 Ft. (MEA 1999)

**M-3 to M-2**  
 GLO = 40 chains or 2640.00 Ft.  
 2856.06 Ft. (MCPC Map)  
 2849.63 Ft. (MEA 1999)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-3 I set a 4" diameter Concrete Monument with a 1/2" x 36" long Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument, MI #345", PS #17623  
 S31°E 96.37' Set Mag Nail & Remon Washer NE face 6" Maple  
 S46°E 183.26' Set Mag Nail & Remon Washer NE face 8" Elm  
 S51°E 92.86' Set Mag Nail & Remon Washer NW face 6" Elm  
 S62°E 83.02' Set Mag Nail & Remon Washer North face 9" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence the position of the original corner.

Signed by: *[Signature]*  
 Surveyor's Michigan License No. 17623

Date 8-5-99

891