

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY & REMONUMENTATION

MAR 17 2000

For corners in

Macomb
 (County)

Located In: Bruce Township Corner Code #

1. Public Land Survey

T 5N R 12E M-5

2. Property Controlling in Section

T ___ R ___
 T ___ R ___
 T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___
 S ___ T ___ R ___
 S ___ T ___ R ___

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-25-99

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Huston K. Kennedy, in a field survey on April 26, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 6" Elm N11 1/2°E 42 Links; 4" Elm N47 1/2°E 58 Links
 1.) 1976-Elrich, PS #18986; Survey L.2653, Pg.381 - Fnd a 1/2" Iron

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod located in the corner of a existing fence, tree & rock row extending to the North, South & West. Corner common to Sections 7 & 18, T5N, R13E, Armada Township (A-5) is located 125.58 feet to the South.

Witnesses from Survey #1 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

M-5 to A-5
 GLO = 8 Links or 5.28 Ft.
 125.58 Ft.

M-5 to M-6
 GLO = 40 chains or 2640.00 Ft.
 No recorded distances
 2700.02 Ft. (MEA 1999)

M-5 to M-4
 GLO = 40 chains or 2640.00 Ft.
 No recorded distances
 2681.63 Ft. (MEA 1999)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 M-5 I replaced the found 1/2" Iron Rod with a 4" diameter Concrete Monument with a 1/2" x 36" long Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument, MI Act #345", PS #17623
 N30°E 14.75' Set Mag Nail & Remon Washer SE face 20" Basswood
 N03°W 23.30' Set Mag Nail & Remon Washer East face 15" Oak
 N66°W 24.20' Set Mag Nail & Remon Washer NE face 14" Ash
 S04°E 28.15' Set Mag Nail & Remon Washer West face 14" Ash
 South 125.58' corner common to Sections 7 & 18, T5N, R13E, Armada Township (A-5)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: *H. Kennedy*
 Surveyor's Michigan License No. 17623

Date 7-5-99



293