

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Macomb</u> (County)	Located In: <u>Bruce Township</u>	Corner Code # <u>M-6</u>
1. Public Land Survey	<u>T 5N</u> <u>R 12E</u>	<u>M-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

SURVEY &  
 REMONUMENTATION

MAR 17 2000

SECTION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 1817-GLO Wampler, D.S.; Set Post 3" Black Ash N10°E 18 Links; 8" Elm S74°W 20 Links
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner was set on a line from M-7 projected thru A-6 and set at the midpoint distance between M-5 to M-7. The corner is located in a existing fence, tree & rock row extending to the North & South. There is no line of occupation extending to the West. The West ¼ corner of Section 18, T5N, R13E, Armada Township (A-6) is located 138.62 feet to the South

**FIELD MEASUREMENTS BETWEEN**

**M-6 to A-6**

No GLO  
 No recorded distances  
 138.62 Ft. (MEA 1999)

**M-6 to M-7**

GLO = 40 chains or 2640.00 Ft.  
 No recorded distances  
 2700.02 Ft. (MEA 1999)

**M-6 to M-5**

GLO = 40 chains or 2640.00 Ft.  
 No recorded distances  
 2700.02 Ft. (MEA 1999)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-6 I set a 4" diameter Concrete Monument with a ½" x 36" long Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument, MI Act #345", PS #17623  
 N05°E 28.10' Set Mag Nail & Remon Washer East face 31" Oak  
 N61°E 12.40' Set Mag Nail & Remon Washer SE face 34" Oak  
 S21°E 12.05' Set Mag Nail & Remon Washer NE face 13" Cherry  
 S30°E 23.00' Set Mag Nail & Remon Washer SW face 26" Oak  
 South 138.62' West ¼ corner of Section 18, T5N, R13E, Armada Township (A-6)



ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-29-99  
William E. Soderberg  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]  
 Surveyor's Michigan License No. 17623

Date 7-5-99

894