

1036517  
 LIBER 9095 PAGE 385  
 09/09/1999 01:53:03 P.M.  
 MACOMB COUNTY, MI.  
 CARMELLA SABAUGH, REG/DEEDS

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb  
 (County)

Located In: Bruce Township Corner Code #

1. Public Land Survey	T <u>5N</u>	R <u>12E</u>	<u>M-9</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

**SURVEY & RE-MONUMENTATION**

MAR 17 2000

SECTION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on April 15, 1999, hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 1817-GLO Wampler, D.S.; Set Post 5" Butternut N6°W 5 Links; 4" Thorn S14°W 72 Links
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner was recovered based upon the tax description for parcel 01-25-200-005 and verified by the monumentation as found in "MALLARD CREEK ESTATES" MCCP#444. The corner as recovered is located in an old fence line extending to the North and is 69.26 feet North of the existing centerline of 34 Mile Road extending to the East & West, which has a gravel surface. Corner common to Sections 19 & 30, T5N, R13E, Armada Township (A-9) is located 69.26 feet to the South.

**FIELD MEASUREMENTS BETWEEN**

**M-9 to A-9**  
 GLO = 8 Links or 5.28 Ft.  
 69.26 Ft. Tax Description Parcel 01-25-200-005  
 69.26 Ft. (Set)

**M-9 to L-9**  
 GLO = 40.50 chains or 2673.00 Ft.  
 2666.09 Ft. (MCPC Map)  
 2666.42 Ft. (MEA 1999)  
 (L-9 has not submitted for approval)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 6-29-99

William E. Soderberg  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN



(Con't on back side)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-9 I set a 4" diameter Concrete Monument with a 1/2" x 36" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument, MI Act #345", PS #17623  
 Due North 15.73' Set Mag Nail & Remon Washer West face 11" Box Elder  
 Due South 18.08' Set Mag Nail & Remon Washer East face 9" Ash  
 S85°E 21.49' Set Mag Nail & Remon Washer South face 9" Ash  
 N05°E 21.68' Set Mag Nail & Remon Washer West face 13" Ash  
 South 69.26' corner common to Sections 19 & 30, T5N, R13E, Armada Township (A-9)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]  
 Surveyor's Michigan License No. 17623

Date 9-1-99

9x ✓

296

SURVEY &  
REMONUMENTATION

BRUCE TOWNSHIP  
T5N R12E M-9

MAR 17 2000

M-9 to M-8

GLO = 40 chains or 2640.00 Ft.  
No recorded distances  
2666.51 Ft. (MEA 1999)

SECTION

M-9 to M-10

GLO = 40 chains or 2640.00 Ft.  
2741.73 Ft. Tax Description Parcel 01-25-200-005 (M-9 to A-10) for Bruce Twp. (1-5)  
2689.13 Ft. (MCPC Map) (A-9 to A-10) for Armada Twp. (2-N)  
2741.73 Ft. or 2672.47 Ft. (MCPC Map) (M-9 to A-10) Bruce Twp. (2-N)  
2698.38 Ft. (MEA 1999)