

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb  
 (County)

Located in: Bruce Township Corner Code # \_\_\_\_\_

1. Public Land Survey  
 T 5N R 12E M-10  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling in Section  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec.  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

SURVEY &  
 REMONUMENTATION

MAR 17 2000

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 6-29-99

William E. Soderberg  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN  
 Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 1817-GLO Wampler, D.S.; Set Post 12" Sugar Tree N26°W 13 Links; 12" Beech S20°W 23 Links
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner has not been perpetuated and was recovered on the link from M-11 projected A-10 and setting the corner at the midpoint between M-9 & M-11. The corner as recovered is in a oak fence, tree & rock row extending to the North & South. The West 1/4 corner of Section 30, T5N, R13E, Armada Township (A-10) is located 60.04 feet to the South.

A-11 to A-10  
 2704.39 Ft. (MCPC Map)  
 2704.39 Ft. (1999 MEA)

M-10 to A-11  
 GLO = 40 chains or 2640.00 Ft.  
 M-11 to A-10 = 2638.38 Ft. (MCPC Map)  
 M-11 to A-11 = + 66.01 Ft. (MEA 1999)  
 Total 2704.39 Ft. (MCPC Map)

M-10 to M-11  
 GLO = 40 chains or 2640.00 Ft.  
 No recorded distances  
 2698.38 Ft. (MEA 1999)

M-10 to A-10  
 No GLO  
 60.04 Ft. (MEA 1999)

M-10 to M-9  
 GLO = 40 chains or 2640.00 Ft.  
 2741.73 Tax Description Parcel 01-25-200-005 (M-9 to A-9)  
 2741.73 Ft. or 2672.47 Ft. (MCPC Map) A-10 to M-9 Bruce Twp. (I-5)  
 2689.73 Ft. (MCPC Map) Armada Twp. (N-2)  
 2698.38 Ft. (MEA 1999)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 M-10 I set a 4" diameter Concrete Monument with a 1/2" x 24" Iron Rod w/2" diameter aluminum cap 13621ped from County Monument, MI Act #345, PS #17623  
 N08°E 14.34' Set Mag Nail & Remon Washer NW face 7" Elm  
 N10°W 23.95' Set Mag Nail & Remon Washer East face 24" Cherry  
 N44°W 15.16' Set Mag Nail & Remon Washer NE face 8" Elm  
 S56°W 15.92' Set Mag Nail & Remon Washer NW face 10" Box Elder  
 South 60.04' West 1/4 corner of Section 30, T5N, R13E, Armada Township (A-10)



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: Huston K. Kennedy Date 9-1-99  
 Surveyor's Michigan License No. 17623

597