

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
 REMONUMENTATION

APR 07 1998

For corners in

<u>Macomb</u> (County)	Located In: <u>Bruce Township</u>	Corner Code # <u>N-11</u>
1. Public Land Survey	T <u>5N</u> R <u>12E</u>	<u>N-11</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

SECTION  
 ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-23-97  
William E. Soderberg  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on 6/17, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 1817-GLO Wampler, D.S.; Set Post, No Witnesses

- 1.) 1987-Dunn, PS #28408; LCRC L.4335, Pg.657 - Fnd 1/2" Iron Rod w/cap #30085
- 2.) 1978-Kobs, PS #14097; Survey L.2923, Pg.829 - Fnd chiseled "+" in a large rock
- 3.) 1978-Kobs, PS #14097; Survey L.2923, pg.827 - Fnd chiseled "+" in a large rock, used same wit as Survey #2
- 4.) 1995-King, PS #30085; Survey L.6840, pg.868 - Fnd 1/2" Bar w/cap #30085, no witnesses
- 5.) Pate, Hirn & Boque, Inc. Construction Plans for Powell Road

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd The corner has since been perpetuated with 1/2" Iron Rod w/cap #30085 in the existing centerline of Powell Road, which has a concrete surface, also the existing centerline of 33 Mile Road extending to the West, which has a gravel surface. A tree-fence row extending to the North. Corner common to Sections 30 & 31, T5N, R13E, Armada Township, (A-11) is located 66.01 feet to the South. Also found second 1/2" Iron Rod 61.74 feet to the South.

Witnesses from LCRC #1, 2 and Survey #5 were used to recover and verify the location of the found 1/2" Iron Rod w/cap #30085.

See back side of LCRC for Field Measurements

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623 in a new Monument Box  
 Due North 27.48' Set PK & Remon Washer East face 9" Elm South 61.74 feet found 1/2" Iron Rod  
 N87°W 91.28' Set PK & Remon Washer South face 16" Elm  
 S43°W 98.46' Set PK & Remon Washer SW face Power Pole  
 S44°E 108.56' Set PK & Remon Washer SW face Power Pole  
 South 66.01 feet, corner common to Section 30 & 31, T5N, R13E, Armada Township (A-11)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available position of the original corner.

Signed by [Signature]  
 Surveyor's Michigan License No. 17623

Date 10-4-97



735

FIELD MEASUREMENTS BETWEEN

M-11 to A-11

GLO = 1 chain or 66.00 Ft.  
GROUND-MEA = 66.01 Ft. (A-11) also found second 1/2" Iron Rod 61.74 feet to the South  
Construction Plans for Powell Road = 68.29 Ft.

M-11 to L-11

GLO = 39.84 chains or 2629.44 Ft.  
Survey recorded in Liber 2923, Page 829 (1/17/78) = 2629.36 Ft.  
M.C.P.C. Map (I-S) = 2635.73 Ft.  
GROUND-MEA = 2629.43 Ft.  
GRID-MEA = 2628.96 Ft. or GROUND CAL. = 2629.21 Ft.

M-11 to M-12

GLO = 40 chains or 2640.00 Ft.  
GROUND-MEA = 2743.70 Ft.  
Construction Plans for Powell Road = 2743.80 Ft.  
GRID-MEA = 2743.43 Ft. or GROUND CAL. = 2743.68 Ft.

C0619503 LIBER:07769 PAGE:490 08:30A 12/12/1997  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS