

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb
 (County)

Located In: Armada Township Corner Code #

1. Public Land Survey	T <u>5N</u>	R <u>13E</u>	<u>A-2</u>
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

SURVEY &
 REMONUMENTATION

MAR 17 2000

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Preston, D.S.; No post was set, no witnesses
 1.) 1981-Ruszala, PS #21581; Survey L.3327, Pgs. 218 & 219 - Only the approximate position of the corner is shown
 2.) 1990-Ruszala, PS #21581; Survey L.4967, Pg.175 - Corner not shown
 3.) 1997-Northeast Survey & Associates., Unrecorded Survey - Fnd 1/2" Iron Rod 8' West of centerline of drain
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod located 10 feet West of a North-South ditch, also 20 feet West of a North-South fence line. The distance shown on the MCPC Map (2-A), verify the measured distance. The East 1/4 corner of Section 1, T5N, R12E, Bruce Township (M-2) is located 229.97 feet to the North.
- I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

A-2 to A-1
 No GLO
 M.C.P.C. Map = 2943.57 Ft.
 2943.68 Ft. (MEA 1999)
 Unrecorded Survey by Northeast Survey dated 3/21/97 = 2943.57 Ft.

A-2 to B-2 (B-2 not an approved corner)
 M.C.P.C. Map = 1957.13 Ft.
 1962.04 Ft. (MEA 1999)
 Unrecorded Survey by Northeast Survey dated 3/21/97 = 1959.64 Ft.

A-2 to A-3
 No GLO
 M.C.P.C. Map = 2619.12 Ft.
 2619.66 Ft. (MEA 1999)

A-2 to M-2
 No GLO
 No recorded distances
 229.97 Ft. (MEA 1999)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-2 I replaced the found 1/2" Iron Rod with a 4" diameter Concrete Monument with a 1/2" iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument, MI Act #345", PS #17623
 S21°E 25.95' Set Mag Nail & Remon Washer SW face 16" Maple
 S71°W 19.50' Set Mag Nail & Remon Washer North face 38" Maple
 N49°W 27.90' Set Mag Nail & Remon Washer NE face 18" Ash
 Due North 41.45' Set Mag Nail & Remon Washer West face 17" Ash
 North 229.97' East 1/4 corner Section 1, T5N, R12E, Bruce Township (M-2)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 7-27-99

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence the position of the original corner.

Signed by: [Signature]
 Surveyor's Michigan License No. 17623

Date 7-29-99

293