

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &
 REMONUMENTATION**

MAR 17 2000

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER
 GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
 PUBLIC ACT 345 OF 1990 AT A MEETING HELD
 ON 7-27-99

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

For corners in

<u>Macomb</u> (County)	Located In: <u>Armada Township</u>	Corner Code # <u>A-3</u>
1. Public Land Survey	T <u>5N</u> R <u>13E</u>	<u>A-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on March 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Preston, D.S.; No post was set, no witnesses
 1.) 1981-Ruszała, PS #21581; Survey L.3326, Pgs. 68 & 69
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner was recovered based upon the tax description for Parce 01-01-400-003 and is located 10 feet West of the center of a ditch extending to the North & South. No line of occupation to the East & West. M-3 (Bruce Township) as recovered, is a common corner with A-3 (Armada Township).

I found no other evidence to dispute the recovered position of this corner.

FIELD MEASUREMENTS BETWEEN

A-3 to A-2
 No GLO
 M.C.P.C. Map = 2619.12 Ft.
 2619.66 Ft. (MEA 1999)

A-3 to A-4
 No GLO
 M.C.P.C. Map = 2652.84 Ft.
 2652.75 Ft. (MEA 1999)

A-3 to B-3
 GLO = 29.50 chains or 1947.00 Ft.
 1948.26 Ft. or 1960.36 Ft. per description per 02-07-1003
 1942.98Ft. (MEA 1999)

A-3 to M-3
 GLO = 30 Links or 19.80 Ft.
 M-3 (Bruce Twp.) as recovered, is a common corner to A-3



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-3 I set a 4" diameter Concrete Monument with a 1/2" x 36" long iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument, MI #345", PS #17623
 S31°E 96.37' Set Mag Nail & Remon Washer NE face 6" Maple
 S46°E 183.26' Set Mag Nail & Remon Washer NE face 8" Elm
 S51°E 92.86' Set Mag Nail & Remon Washer NW face 6" Elm
 S62°E 83.02' Set Mag Nail & Remon Washer North face 9" Elm

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: *Huston Kennedy*
 Surveyor's Michigan License No. 17623

Date 8-5-99

884