

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Macomb</u> (County)	Located In: <u>Armada Township</u>	Corner Code # <u>A-4</u>
1. Public Land Survey	T <u>5N</u> R <u>13E</u>	<u>A-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

SURVEY &  
 REMONUMENTATION

MAR 17 2000

SECTION

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on March 23, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
 1817-GLO Preston, D.S.; No post was set, no witnesses  
 1.) 1987-King, PS #30085; LCRC L.4220, Pg.485 - Fnd a Iron w/cap #14097  
 2.) 1986-King, PS #30085; Unrecorded Survey - Fnd a 1/2" Iron w/cap #30085, used same wit as 1987 LCRC
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 1998-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod w/cap #30085 located in a tree-fence row extending North & South, also located 125 feet South of the existing centerline of Reid Road extending to the West & East which has a gravel surface. The corner as found is 0.37 feet West of the range line and was reset on a line between M-4 and M-5. East 1/4 corner of Section 12, T5N, R12E, Bruce Township (M-4) is located 137.04 feet to the North.

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod w/cap #14097.

I accepted the found 1/2" Iron Rod w/cap #14097 as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

A-4 to A-3  
 No GLO  
 2652.84 Ft. MCPC Map  
 2652.75 Ft. (MEA 1999)

A-4 to M-4  
 No GLO  
 136.68 Ft. (MCPC Map)  
 137.04 Ft. (MEA 1999)

A-4 to A-5  
 No GLO  
 2670.18 Ft. (MEA 1999)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 A-4 I set a 4" diameter Concrete Monument with 1/2" Iron Rod 36" long w/2" diameter aluminum cap stamped Macomb County Monument MI Act #345 #17623 on the range line  
 N05°E 2.45' Set Mag Nail & Remon Washer West face 18" Cherry  
 N34°W 24.60' Set Mag Nail & Remon Washer NE face 11" Oak  
 N65°E 8.00' Set Mag Nail & Remon Washer SE face 16" Oak  
 S48°E 9.32' Set Mag Nail & Remon Washer NE face 12" Oak  
 North 137.04' East 1/4 corner of Section 12, T5N, R12E, Bruce Township (M-4)  
 West 0.37' found 1/2" Iron Rod w/cap #30085

ACCEPTED BY THE MACOMB COUNTY SURVEY PEEI GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-25-99

William E. Soderberg  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]  
 Surveyor's Michigan License No. 17623

Date 7-29-99

485