

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb
 (County)

Located in: Armada Township Corner Code #

**SURVEY &
 REMONUMENTATION**

MAR 17 2000

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER
 GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
 PUBLIC ACT 345 OF 1990 AT A MEETING HELD
 ON 5/25/99

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

- | | | | |
|---------------------------------------|-------------|--------------|------------|
| 1. Public Land Survey | T <u>5N</u> | R <u>13E</u> | <u>A-5</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling
in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous
Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 26, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Preston, D.S.; No post was set, no witnesses
 1.) 1972-Kobs, PS #14097; LCRC L.2293, Pg.272 - Fnd a 1/2" Iron Bar.
 2.) 1972-Kobs, PS #14097; Survey L.2293, Pg.265 - Fnd 1/2" Iron Bar, used same wit as 1972 LCRC
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" capped Iron Rod located in a existing fence, tree & rock row extending to the North, South & East. Corner common to Sections 12 & 13, T5N, R12E, Bruce Township (M-5) is located 125.58 feet to the South. The corner as found is 0.19 feet West of the range line and was reset on the line between M-5 and M-6.

Witnesses from LCRC #1 & Survey #2 were used to recover and verify the location of the found 1/2" capped Iron Rod.
 I accepted the found capped 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

A-5 to A-4
 No GLO
 No recorded distances
 2670.18 Ft. (MEA 1999)

A-5 to M-5
 GLO = 8 Links or 5.28 Ft.
 No recorded distances
 125.58 Ft. (MEA 1999)

A-5 to A-6
 No GLO
 Recorded Survey in Liber 2293, page 265 = 2713.12 Ft.
 M.C.P.C. Map = 2713.72 Ft. (MEA 1999)
 2713.32 Ft. (MEA 1999)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-5 I replaced the found capped 1/2" Iron Rod with a 4" Concrete Monument with a 1/2" x 36" long Iron Rod w/2" diamete aluminum cap stamped "Macomb County Monument, MI Act #345", PS #17623 on the range line
 N53°W 10.15' Set Mag Nail & Remon Washer SW face 10" Ash
 N35°E 24.40' Set Mag Nail & Remon Washer NW face 12" Bass Wood
 Due North 38.35' Set Mag Nail & Remon Washer West face 27" Ash
 S37°W 24.20' Set Mag Nail & Remon Washer NE face 10" Ash
 South 125.58' corner common to Sections 12 & 13, T5N, R12E, Bruce Township (M-5)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence c the position of the original corner.

Signed by: Huston K. Kennedy Date 7-5-99
 Surveyor's Michigan License No. 17623

286