

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

**SURVEY &
 REMONUMENTATION**

For corners in

Macomb Located in: Armada Township Corner Code #
 (County)

1. Public Land Survey T 5N R 13E A-6
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

MAR 17 2000

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 5-25-99

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Preston, D.S.; No post was set, no witnesses
 1.) 1972-Kobs, PS #14097; LCRC L.2293, Pg.274 - Fnd 1/2" Iron Bar at a Anchor Post
 2.) 1984-Kobs, PS #14097; LCRC L.3705, Pg. 151 - Fnd a 1/2" Iron Bar w/cap #14097 at an Anchor Post
 3.) 1972-Kobs, PS #14097; Survey L.2293, Pg.265 - Fnd 1/2" Iron Bar, used same wit as 1972 LCRC
 4.) 1991-King, PS #30085; Survey L.5253, Pg.179 - Fnd 1/2" Iron Bar, used same wit as 1984 LCRC
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" capped Iron Rod in a fence-tree row extending to the North, South & East. A-6 is located on the line between M-7 and M-6. The East 1/4 corner of Section 13, T5N, R12E, Bruce Township (M-6) is located 138.62 feet to the North.

Witnesses from LCRC #2 were used to recover and verify the location of the found 1/2" capped Iron Rod.

I accepted the found 1/2" capped Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

A-6 to A-5 No GLO 2713.72 Ft. (MCPC Maps) Survey recorded in Liber 2293, page 265 = 2713.12 Ft. 2713.32 Ft. (MEA 1999)	A-6 to A-7 No GLO 2671.87 Ft. MCPC Maps) Survey recorded in Liber 5253, page 179 = 2671.87 Ft. 2671.92 Ft. (MEA 1999)	A-6 to M-6 No GLO No recorded distances 138.62 Ft. (MEA 1999)
--	--	---

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-6 I replaced the found 1/2" capped Iron Rod with a 4" Concrete Monument with a 1/2" X 36" long Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument, MI Act #345", PS #17623
 N15°W 26.60' Set Mag Nail & Remon Washer SW face 10" Thornapple
 S80°E 13.75' Set Mag Nail & Remon Washer SE face 12" Maple
 S29°E 17.12' Set Mag Nail & Remon Washer SW face 7" Bean Hop
 S31°W 9.18' Set Mag Nail & Remon Washer NW face 12" Maple
 North 138.62' East 1/4 corner of Section 13, T5N, R12E, Bruce Township (M-6)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: Huston K. Kennedy
 Surveyor's Michigan License No. 17623

Date 7-5-99



887