

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb
(County)

Located In: Armada Township Corner Code #

- 1. Public Land Survey T 5N R 13E A-7
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

109180P
LIBER 9267 PAGE 956
12/27/1999 01:11:35 P.M.
MACOMB COUNTY, MI
CARMELLA SABAUGH, REG/DEEDS

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on April 15, 1999 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 - 1.) 1984-Kobs, PS #14097; LCRC L.3705, Pg.151 - Fnd a 1/2" Iron Bar
 - 2.) 1988-Avey, PS #30076; LCRC L.4353, Pg.428 - Fnd a 1/2" Form Pin
 - 3.) 1986-Kobs, PS #14097; Survey L.4077, Pgs.594-596 - Fnd a 1/2" Iron Bar w/cap #14097
 - 4.) 1988-Kobs, PS #14097; Survey L.4375, Pg.741 - Fnd a 1/2" Iron Bar w/cap #14097
 - 5.) 1991-King, PS #30085; Survey L.5253, Pg.179 - Fnd a 1/2" Iron Bar, used same wit as 1984 LCRC
 - 6.) 1993-King, PS #30085; Unrecorded Survey - Fnd 1/2" Iron Bar, used same wit as 1984 LCRC
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod located in the existing centerline of Armada Center Road extending to the East & West, which has a bituminous surface. There is a fence/tree line extending to the North. The corner as found is 0.56 feet East of the range line and was reset on the range line. Corner common to Sections 13 & 24, T5N, R12E, Bruce Township (M-7) is located 110.77 feet to the North.

Witnesses from LCRC #1, 2, Surveys #3 & 4 were used to recover and verify the location of the found a 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

Field measurements see back side

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped Macomb County Professional Surveyor 17623

Monument, MI Act #345", PS #17623 in a new Monument Box

N02°W 85.75' Set Mag Nail & Remon Washer West face 6" Oak

S18°E 34.99' Set Mag Nail & Remon Washer NE face 31" Ash

S09°W 92.88' Set Mag Nail & Remon Washer East face 9" Elm

S64°W 90.05' Set Mag Nail & Remon Washer NW face 32" Apple

North 110.77' corner common to Sections 13 & 24, T5N, R12E, Bruce Township (M-7)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
Surveyor's Michigan License No. 17623

Date 9-10-99



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 23, 1971; REVISED MAY 14, 1975; REVISED JAN., 1983; REVISED OCT., 1995

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8/31/99
[Signature]
WILLIAM E. SODERBERG, P.S., CHAIRMAN

94

172

FIELD MEASUREMENTS BETWEEN

A-7 to A-6

No GLO
2671.87 Ft. (MCPC Maps)
Survey recorded in Liber 5253, page 179 = 2671.87 Ft.
2671.92 Ft. (MEA 1999)

A-7 to A-8

No GLO
Survey recorded in Liber 4077, pages 594-596 = 2699.89 Ft.
Unrecorded Survey by Donald King, PS #30085 dated 4/20/93 = 2699.89 Ft.
2699.91 Ft. (MEA 1999)

A-7 to M-7

GLO = 1.50 chains or 99.00 Ft.
LCRC recorded in Liber 4077, page 545 = 1107 Ft.
Survey recorded in Liber 4077, pages 594-596 = 110.77 Ft.
Survey recorded in Liber 4375, page 741 = 110.77 Ft.
Unrecorded Survey by Donald King, PS #30085 dated 4/20/93 = 110.77 Ft.
110.77 Ft. (MEA 1999)

**SURVEY &
REMONUMENTATION**

MAR 17 2000

SECTION