

SURVEY & REMONUMENTATION

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1036515
LIBER 9095 PAGE 381
01:48:24 P.M.
MAY 1999
MACOMB COUNTY, MI
CARMELLA SABAUGH, REG/DEEDS

For corners in

Macomb
(County)

Located In: Armada Township
Corner Code #

	T 5N	R 13E	A-9
1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 6-29-99

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4			3		2		1	
3													
4	7		8		9			10		11		12	
5													
6	18		17		16			15		14		13	
7													
8	19		20		21			22		23		24	
9													
10	30		29		28			27		26		25	
11													
12	31		32		33			34		35		36	
13													

I, Huston K. Kennedy, in a field survey on April 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Preston, D.S.; No post was set, no witnesses

- 1.) 1995-King, PS #30085; LCRC L.6613, Pg.525 - Fnd a 5/8" Iron in a Monument Box
- 2.) 1976-Kobs, PS #14097; Survey L.2681, Pg.129 - Fnd a 1/2" Iron Bar
- 3.) 1989-King, PS #30085; Survey L.4729, Pg.194 - Fnd a 1/2" Iron Bar, used same wit as 1976 Survey
- 4.) 1995-King, PS #30085; Survey L.6628, Pg.781 - Fnd a 1/2" Iron Bar, used same wit as 1995 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 5/8" Iron Rod in a Monument Box located in the existing centerline of 34 Mile Road extending to the East & West, which has a gravel surface, also 80 feet West of the center of the North branch of the Clinton River extending to the North & South. A old fence-free row extends to the North & South. Corner common to Sections 24 & 25, T5N, R12E, Bruce Township (M-9) and is located 69.26 feet to the North.

Witnesses from LCRC #1 & Survey #2 were used to recover and verify the location of the found a 5/8" Iron Rod in a Monument Box.

I accepted the found 5/8" Iron Rod in a Monument Box as the best evidence of the original corner position.

Field measurements on back side of LCRC

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
A-9 I replaced the found 5/8" Iron Rod with a 1/2" x 24" Iron Rod w/2" diameter aluminum cap stamped Macomb County Monument, MI Act #345", PS #17623 in a existing Monument Box
Due North 51.88' Set Mag Nail & Remon Washer East face 9" Ash
N37°E 93.78' Set Mag Nail & Remon Washer SE face 19" Ash
N63°W 175.58' Set Mag Nail & Remon Washer South face 33" Maple
S84°W 83.73' Set Mag Nail & Remon Washer NW face 17" Ash
North 69.26' corner common to Sections 24 & 25, T5N, R12E, Bruce Township (M-9)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: H.K. Kennedy
Surveyor's Michigan License No. 17623

Date 9-1-99



9x2

888

**SURVEY &
REMONUMENTATION**

MAR 17 2000

SECTION

ARMADA TOWNSHIP
T5N R13E A-9

FIELD MEASUREMENTS BETWEEN

A-9 to A-8

No GLO
2657.22 Ft. (MCPC Map)
Survey recorded in Liber 2681, page 129 = 2657.16 Ft.
Survey recorded in Liber 6228, page 781 = 2657.50 Ft.
2657.42 Ft. (MEA 1999)

A-9 to A-10

No GLO
2689.13 Ft. (MCPC Map) Armada Twp. (A-9 to A-10) (N-2)
2741.73 Ft. or 2672.47 Ft. (MCPC Map) Bruce Twp. (I-S) (M-9 to A-10)
2672.47 Ft. Tax Description for Parcel 01-25-200-005
2689.17 Ft. (MEA 1999)

A-9 to M-9

GLO = 8 Links or 5.28 Ft.
69.26 Ft. Tax Description for Parcel 01-25-200-005
69.26 Ft. (Set)