

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb
 (County)

Located in: Armada Township Corner Code #

- | | | | |
|------------------------------------|-------------|--------------|-------------|
| 1. Public Land Survey | T <u>5N</u> | R <u>13E</u> | <u>A-10</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

SURVEY & REMONUMENTATION

MAR 17 2000

SECTION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 15, 1999 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Preston, D.S.; No post was set, no witnesses
 1.) 1993-King, PS #30085; Survey L.5831, pg.325 - Fnd a 1/2" Pipe
 2.) 1977-Detroit Edison Unrecorded Survey - Fnd a Iron Pipe, no witnesses
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Pipe beside a capped 1/2" Iron Rod, PS #12043 located in a old fence, rock & tree row extending to the North, South & East, also 100 feet North of the center of an overhead Detroit Edison Transmission Line extending to the East & West. The East 1/4 corner of Section 25, T5N, R12E, Bruce Township (M-10) is located 60.04 feet to the North.

Witnesses from Survey #1 were used to recover and verify the location of the found 1/2" Iron Pipe.

I accepted the found 1/2" Iron Pipe as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

A-10 to A-9
 No GLO
 2689.13 Ft. (MCPC Map)
 2689.17 Ft. (MEA 1999)

A-10 to M-10
 No GLO
 60.04 Ft. (MEA 1999)

A-10 to A-11
 No GLO
 2704.36 Ft. (MCPC Map)
 2704.36 Ft. (MEA 1999)
 Unrecorded Survey by Detroit Edison dated 12/1/77 = 2704.37 Ft.

ACCEPTED BY THE MACOMB COUNTY SURVEYORS GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 6/27/1999
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-10 I replaced the found 1/2" Iron Pipe beside a capped 1/2" Iron Rod PS #12043 with a 4" diameter Concrete Monument with a 1/2" x 36" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument, MI Act #345", PS #17623
 N53°E 11.35' Set Mag Nail & Remon Washer NW face 12" Cherry
 N27°W 14.58' Set Mag Nail & Remon Washer SW face 9" Cherry
 S17°E 14.35' Set Mag Nail & Remon Washer East face 16" Ash
 Due East 8.51' Set Mag Nail & Remon Washer North face 18" Walnut
 North 60.04' East 1/4 corner of Section 25, T5N, R12E, Bruce Township (M-10)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
 Surveyor's Michigan License No. 17623

Date 7-5-99

RB9