

**SURVEY &  
REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

APR 07 1998

For corners in

<u>Macomb</u> (County)	Located in: <u>Armad Township</u>	Corner Code # <u>A-12</u>
1. Public Land Survey	T <u>5N</u> R <u>13E</u>	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**SECTION**

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8/5/97

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on 6/17, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1817-GLO Wampler, D.S.; Post not set, no witnesses
- 1.) 1987-Dunn, PS #28408; LCRC L.4335, Pg.658 - Fnd 1/2" Iron Rod w/cap
- 2.) 1992-Avey, PS #30076; LCRC L.5700, Pg.480 - Fnd Capped 1/2" Bar in a Monument Box
- 3.) 1979-Kobs, PS #14097; Survey L.3162, Pg.632 - Fnd 1/2" Pipe
- 4.) 1992-Urban Land Consultants; Unrecorded Survey - Fnd 1/2" Bar in a Monument Box, used same wit as 1992 LCRC
- 5.) 1996-Kennedy, PS #17623; Unrecorded Survey - Fnd 1/2" Iron Rod in a Monument Box

C0585107 LIBER:07661 PAGE:5 09:11A 10/01/1997  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Pipe in a Monument Box that is located in the existing centerline of Powell Road extending to the North & South, which has a concrete surface. There is a power pole extending to the East. There is no line of occupation to the West. This corner has been accepted and used as common corner with the East 1/4 corner of Section 36, T5N, R12E, Bruce Township (A-12).

Witnesses from LCRC #1, 2 & Survey #3 were used to recover and verify the location of the found 1/2" Iron Pipe in a Monument Box.

See back side of LCRC for Field Measurements

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- A-12 I replaced the found 1/2" Iron Pipe with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623 in a existing Monument Box
- N23°W 107.67' Set PK & Remon Washer NE face Power Pole
- N36°E 95.40' Set PK & Remon Washer NW face 10" Hickory
- S54°W 68.50' Set PK & Remon Washer SE face 12" Poplar
- S88°E 57.61' Set PK & Remon Washer South face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence position of the original corner.

Signed by *Huston K. Kennedy*  
Surveyor's Michigan License No. 17623

Date 8-8-97



757

C0585107 LIBER:07661 PAGE:6 09:11A 10/01/1997  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

FIELD MEASUREMENTS BETWEEN

A-12 to A-11

No GLO  
GROUND-MEA = 2681.91 Ft.  
GRID-MEA = 2681.69 Ft. or GROUND CAL. = 2681.93 Ft.

A-12 to A-13

No GLO  
M.C.P.C. Map (2-31E) = 2659.07 Ft.  
Survey, L.3162, Pg.632 dated 7/79 = 2659.07 Ft.  
Survey Unrecorded, dated 7/92 = 2659.36 Ft.  
Survey Unrecorded, dated 7/96 = 2659.43 Ft.  
GROUND-MEA = 2659.50 Ft.  
GRID-MEA = 2659.12 Ft. or GROUND CAL. = 2659.36 Ft.