

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB
 (County)

RICHMOND TOWNSHIP
 Located In: Corner Code #

1. Public Land Survey T 5 N R 14 E M-8
 T ___ R ___
 T ___ R ___
 T ___ R ___
 2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___
 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___
4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

SURVEY &
 RE-MONUMENTATION
 MAR 15 1999
 SECTION
 Register of Deeds Stamp & File Number

I, ROBERT H. BIRKETT, in a field survey on JUNE 8, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 FOUND 5/8" IRON, 3' WEST OF CENTER GRAVEL STODDARD ROAD AT A DEPTH OF 0.1'.

22.00' (1, 2, 4) - 21.92' (5) - 22.10' - WEST - P.K. NAIL IN RAIL ROAD TIE FENCE POST. (FND. 21.17').
 1, 2 & 4) S. W. - 83.25' - P.K. NAIL IN 42" OAK. (FND. 83.41').

FIELD MEASUREMENTS

M-8 TO M-7, GLO (1817) - 40 CHAINS (2640')
 NO PREVIOUS RECORDED DISTANCE
 RE-MONUMENTATION (1998) - 2673.77'

M-8 TO M-9, GLO (1817) - 40 CHAINS
 MELCHING (1971) - 2682.00'
 LANSKY (1977 & 1980) - 2682.00'
 RE-MONUMENTATION (1998) - 2682.24'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-8 REPLACED 5/8" IRON WITH A 3/4" X 24" RE-BAR WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT, MI ACT 345, #41094, M-8".

- AZ. 5° - 165.11' - FOUND P.K. NAIL WITH TAG #30103 IN SOUTHWEST FACE 15" ASH.
 AZ. 150° - 80.30' - FOUND P.K. NAIL WITH TAG #30103 IN SOUTHWEST FACE 12" ASH.
 AZ. 165° - 142.31' - FOUND P.K. NAIL TOP NORTH MOST GUARD RAIL POST EAST SIDE STODDARD ROAD
 AZ. 192° - 83.41' - FOUND P.K. NAIL WITH TAG #30103 IN NORTHEAST FACE 48" OAK.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER BOARD AS THE OFFICIAL CORNER UNDER MICHIGAN ACT 345 OF 1990 AT A MEETING HELD ON 8/27/98
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Signed by Robert H. Birkett Date 11-24-98
 Surveyor's Michigan License No. 41094



841

SURVEY &
MONUMENTATION

MAR 15 1999

A. Description of original monument and accessories and/or subsequent restoration:

FROM FRONT

SECTION

M-8 1817, W. PRESTON, GLO, SET POST

- 1) 1971, C. MELCHING #14767, IRON ROD, SURVEYS L. 2285, P. 423, 425 & 426, M.C.R.
- 2) 1972, C. MELCHING #14767, 5/8" ROD, L.C.R.C. L. 2285, P. 453, M.C.R.
- 3) 1974, H. KOBBS #14097, 5/8" IRON BAR, SURVEY L. 2486, P. 516, M.C.R.
- 4) 1977, J. LANSKY #18659, IRON ROD, SURVEY L. 2875, P. 700, M.C.R.
- 5) 1974, H. KOBBS #14097, 5/8" IRON BAR, SURVEY L. 6 SUR., P. 346, S.C.C.R.
- 6) 1980, J. LANSKY #18659, IRON ROD, SURVEY L. 3216, P. 625, M.C.R.

C0863659 LIBER:08565 PAGE:899 09:45A 01/19/1999
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS