

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

RICHMOND TOWNSHIP
 Located In: Corner Code #

MACOMB
 (County)

- | | | | |
|------------------------------------|-------|---------------------|-------------|
| 1. Public Land Survey | | <u>T 5 N R 14 E</u> | <u>M-11</u> |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |

MAR 15 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, ROBERT H. BIRKETT, in a field survey on JUNE 4, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817 W. PRESTON, GLO, SET POST
 1) 1992, G. JAMES #19835, IRON PIPE SET IRON INSIDE, SURVEY L. 5601, P. 110, M.C.R.
 2) 1996, J. NIEDERHAUSER, 1/2" ROD CAP #19835, L.C.R.C. L. 7035, P. 826, M.C.R.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-11 FOUND 1- 1/2" PIPE WITH 1/2" IRON CAP #19835 INSIDE ON A NORTH AND SOUTH FALLEN FENCE.
 1) 6.6' NORTH SPIKE W/CAP IN 12" HICKORY. (FND. 6.60')
 1) 6.0' WEST SPIKE IN 3" APPLE. (FND. 6.02')
 2) S.S.W. 15.66' TO P.K. NAIL IN TWIN 8" ELM. (FND. 15.53')
 2) N.E. 37.94' TO SPIKE IN WEST SIDE 30' OAK. (FND. 37.95')
 2) NORTH 11.95' TO P.K. NAIL IN EAST SIDE 12" ELM. (FND. 11.93')

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9/29/98
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

FIELD MEASUREMENTS

- M-11 TO M-10, GLO - 40 CHAINS (2640')
 JAMES (1992) - 2648.45'
 NIEDERHAUSER (1996) - 2653.14'
 RE-MONUMENTATION (1998) - 2647.64'

M-11 TO M-12, GLO (1817) - 40 CHAINS (2640')
 NO PREVIOUS RECORDED DISTANCE
 RE-MONUMENTATION (1998) - 2700.69'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 REPLACED 1-1/2" PIPE AND IRON WITH A 1/2" IRON ENCASED IN CONCRETE WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT, MI ACT 345, #41094".

- AZ. 10° - 37.95' - FOUND FORM NAIL IN WEST FACE 24" OAK.
 AZ. 90° - 6.60' - FOUND FORM NAIL IN NORTH FACE 10" HICKORY.
 AZ. 180° - 15.53' - FOUND P.K. NAIL IN WEST FACE TWIN 8" ELM.
 AZ. 350° - 6.02' - FOUND FORM NAIL IN SOUTHWEST FACE 9" APPLE.
 AZ. 355° - 11.93' - FOUND P.K. NAIL IN EAST FACE 8" ELM.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Robert H. Birkett Date 11-24-98
 Surveyor's Michigan License No. 41094



844