

**SURVEY &  
REMONUMENTATION**

APR 28 1995

C152274

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 14 AM 10:55

corners in

**MACOMB**

(County)

Located In:  
RICHMOND TWP.

Corner Code #

Public Land Survey

T 5N R 14E

M-13

Property Controlling  
in Section

S      T      R     

Miscellaneous

S      T      R     

Property in Sec.

S      T      R     

MACOMB COUNTY, MI  
REGISTER OF DEEDS

LIBER 6527 PAGE 851

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		6		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

STEVEN E. DUNN, in a field survey on APRIL 4 19 94

herby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore required in the current manual of survey instructions of the United States Department of Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND  
GLO ORIGINAL SURVEY PERFORMED BY PRESTON - 1817

L.C.R.C.	NAME AND NUMBER	DESCRIPTION	DATE
L. 0001 P. 791 (ST. CLAIR COUNTY RECORDS)	HERBERT J. KOBS, #14097	FOUND 1/2" PIPE	MARCH 29, 1973
L. 3204 P. 459	ROBERT L. SMITH, #16052	FOUND 1/2" IRON	JANUARY 25, 1980

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 TOWNSHIP CORNER FOUND 1/2" IRON ROD IN ASPHALT PAVEMENT. COMMON TO : M-1 LENOX TWP., A-1 CASCO TWP., AND A-13 COLUMBUS TWP.  
VERIFIED LOCATION WITH FOUND WITNESSES OF ABOVE L.C.R.C.'s

**FOUND WITNESS TIES**

L.C.R.C. L. 3204 P. 459	N.45°W. 91.98'	NAIL IN SOUTH FACE OF TELEPHONE POLE
	N.30°E. 34.83'	NAIL IN SOUTHEAST FACE OF TELEPHONE POLE
	S.45°W. 34.48'	NAIL IN NORTHEAST FACE OF POWER POLE
L.C.R.C. L. 0001 P. 791 (ST. CLAIR COUNTY RECORDS)	N.W. 47.68'	FORM NAIL AND WASHER IN 18" CHERRY
	N.W. 91.98'	FORM NAIL AND WASHER IN BELL TELEPHONE POLE
	S.W. 34.45'	FORM NAIL AND WASHER IN DETROIT EDISON POLE



Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M-13 T.4N., R.14E. I REPLACED 1/2" IRON ROD WITH 3/4" x 24" IRON ROD WITH 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408" IN A NEW MONUMENT BOX.

**WITNESSES**

N.30°E. 34.83'	FOUND PK. NAIL IN SOUTHEAST FACE OF TELEPHONE POLE.
S.10°E. 58.23'	SET PK. NAIL IN EAST SIDE OF 6" OAK.
S.45°W. 34.45'	FOUND FORM NAIL IN NORTHEAST FACE OF UTILITY POLE.
N.45°W. 91.98'	FOUND FORM NAIL IN SOUTH FACE OF TELEPHONE POLE.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-18-94

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Surveyed by Steven E. Dunn Date Nov. 9, 1994

Surveyor's Michigan License No. 28408