

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>21</u> N. <u>15</u> R. <u>15</u> W.	<u>E-12; G-11; G-12</u>
2. PROPERTY CONTROLLING IN SECTION <u>33</u>	T. <u>21</u> N. <u>15</u> R. <u>15</u> W.	<u>8</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 4, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration
 C. (continued)

- 8
- Set 1"x3' pipe & cedar post w/loc. tag
 - 7" W. Pine N10°E 20.3
 - 8" W. Pine S68°W 30.8

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-12 Reestablished computed position for 1/4 corner common to Sec. 32 & 33, (in river, no point set) equidistant & on line between section corners to N & S. Set wit. pipe's on Sec. Line N & S and 1/4 line's E & W as noted under Item "C".
- G-11 Recovered cabin spike in E-W blacktop road from two witnesses by R.L.S. Ken Ross.
- G-12 Reestablished 1/4 corner per standard B.L.M. instruction. U.S.F.S. squared post at SW corner of red & white pine planting is 39' N and 22' E.
- 8 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12	G-11	G-12
1/4 corner in river, witness irons from 1/4 corner	Fd. cabin spike & added 1 1/2"x24" iron pin	Set DNR mon. & ced. post
set 1 1/2"x36" pipe & post w/loc. tag	16" Oak N32°W 47.18	4" W. Pine N40°E 52.1
S00°03'E 81.60	12" W. Pine S40°E 46.25	4" Maple S10°E 13.9
set 1 1/2"x30" p&p w/loc. tag	11" Oak S43°W 62.30	3" Maple N75°W 4.3
N87°34'W 46.00	set cedar post w/loc. tag	
set 1 1/2"x30" p&ced.post w/loc. tag	Due S 33'	
S88°16'E 222.97		
set 1 1/2"x28"p&ced.post w/loc. tag		
N00°03'W 156.12		

SIGNED BY Carl F. Roser 9-15-76 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

STRONACH TOWNSHIP
MANISTEE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. _____