

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>21</u> <sup>N.</sup> <u>●</u> , R. <u>15</u> <sup>W.</sup> <u>●</u>	<u>C-13; D-13; E-13</u>
2. PROPERTY CONTROLLING IN SECTION <u>32</u>	, T. <u>21</u> <sup>N.</sup> <u>●</u> , R. <u>15</u> <sup>W.</sup> <u>●</u>	<u>13</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ <sup>N.</sup> _____ <u>●</u> , R. _____ <sup>W.</sup> _____ <u>●</u>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 4, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument or accessories and/or subsequent restoration:

C. (continued)

	13
	Set 1 1/4"x24" pipe & cedar post w/loc. tag
7" W. Pine	N75°E 57.3
11" W. Oak	S40°E 23.0

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-13 Found U.S.F.S. concrete mon. for Sec. corner common to Sec. 31 & 32, on S line of T21N, R15W.
- D-13 Found U.S.F.S. concrete monument for S 1/4 corner, Section 32.
- E-13 Found U.S.F.S. concrete monument for section corner common to Sec. 32 & 33 on S line of T21N, R15W.

13 Established center of SE 1/4, Sec. 32, per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13	D-13	E-13
Fd. F.S. concrete monument	Fd. F.S. concrete monument	Fd. F.S. concrete monument
3" W. Oak N30°E 77.71	4" W. Oak N25°E 78.79	7" W. Oak N23°E 72.34
2"x3' pipe N65°E 71.65	4" W. Oak N50°E 54.13	7" B. Oak N57°W 96.62
1 1/4" pipe N65°W 34.94	5" W. Oak N05°W 69.47	2" W. Pine N02°W 38.1
5" W. Oak N04°W 60.56	4"x7' post Due N 33'	4"x7' post Due N 33'
		NE Sec. 6 T20N-R15W
		S87°27'E 230.95

SIGNED BY Carl F. Roser 9-15-76 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ STRONACH TOWNSHIP  
MANISTEE COUNTY