

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|---|-------------------------|
| 1. PUBLIC LAND SURVEY _____ | T. <u>21</u> N. <u>●</u> , R. <u>15</u> W. <u>●</u> | <u>C-12; D-11; D-12</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>32</u> | , T. <u>21</u> N. <u>●</u> , R. <u>15</u> W. <u>●</u> | <u>14; 16</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | , T. _____ N. _____, R. _____ E. _____ W. _____ | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on August 6, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration~~

C. (continued)

| | |
|--|----------------------------|
| 14 | 16 |
| Set 1½"x24" pipe & cedar post w/loc. tag | Set 1½"x23" solid iron pin |
| 6" W. Pine N45°W 13.9 | 6" W. Pine N20°E 80.6 |
| 8" W. Oak S75°W 2.3 | 11" W. Oak N40°E 38.1 |
| | Set cedar post w/loc. tag |
| | Due N 33' |
| | Ctr. E-W gravel road |
| | Due S 12'± |

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-12 Reestablished corner per standard B.L.M. instructions.
- D-11 Found 1" pipe, that fits Walker survey of N line Sec. 32 in 1949 & fits corner position by S.P. reasonably well.
- D-12 Established center of Sec. 32 per standard B.L.M. instructions.
- 14 Established corner per standard B.L.M. instructions.
- 16 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | | |
|---------------------------|---|---|
| C-12 | D-11 | D-12 |
| Set DNR mon. & cedar post | Fd. 1" pipe & added DNR mon. & cedar post | Set 1½"x3' pipe & cedar post w/loc. tag |
| 11" Cedar S40°E 10.3 | 3" W. Pine N42°W 47.0 | 10" W. Pine S10°W 18.4 |
| 9" W. Pine S05°W 27.1 | 6" Oak N75°E 12.6 | 4" W. Pine S85°W 16.0 |
| 13" Cedar S45°W 18.6 | | |

SIGNED BY Carl F. Roser 9-15-76 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ STRONACH TOWNSHIP
MANISTEE COUNTY