

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

| FOR CORNERS OF --:                            | LOCATED IN --:    | CORNER CODE NUMBER                                     |
|---|-------------------|--|
| 1. PUBLIC LAND SURVEY _____                   | T. 21 N. R. 15 W. | B-9; C-9   |
| 2. PROPERTY CONTROLLING IN SECTION 30 _____   | T. 21 N. R. 15 W. | 8  |
| 3. MISCELLANEOUS PROPERTY IN SECTION 30 _____ | T. 21 N. R. 15 W. | XX - 800.14 E of A-10<br>& 661.14 W of Code 8, Sec. 30 |
| 4. LOT NO. _____, RECORDED PLAT _____         |                   |  |
| 5. PRIVATE CLAIMS _____                       |                   |  |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 2, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on July 9, 1975, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration:~~

C. (continued)

XX  
Set 1 1/4" x 36" pipe & cedar post  
w/loc. tag  
4" W. Oak S50°E 21.38  
5" W. Pine S12°W 45.49  
Fd. 1/2" pipe N88°57'W 102.1

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-9 Reestablished 1/4 corner on line between section corners to E & W and at prorated distance to G.L.O. survey.
- C-9 Found iron as previously recovered, witnessed and used by R.L.S. T. Slawinski.
- 8 Established W 1/16 on E-W 1/4 line, on line between 1/4 corner W & center of Sec. 30 E and at prorated distance to G.L.O. survey.
- XX Established the NW corner of the E ten chains of the frl. NW 1/4 of the frl. SW 1/4 of Sec. 30, on line between the W 1/4 & center of Sec. 30, and 800.14' E of W 1/4 corner & 661.14' W of W 1/16 on E-W 1/4 line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| B-9                       | C-9                                       | 8   |
|---------------------------|---|---|
| Set DNR mon. & cedar post | Fd. 1" iron & added DNR mon. & cedar post | Set 1 1/4" x 30" pipe & cedar post w/loc. tag |
| 5" W. Pine N50°W 6.8      | 10" W. Oak S45°W 58.45                    | 4" W. Pine N33°W 20.7                         |
| 5" W. Pine S05°W 50.6     | 6" R. Pine S30°E 80.44                    | 3" W. Pine Due E 10.4                         |
| 8" W. Pine S72°W 71.8     | 6" W. Pine N35°E 74.42                    |   |

SIGNED BY Carl F. Roser 9-15-76 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

STRONACH TOWNSHIP  
MANISTEE COUNTY