

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>21</u> N. <u>15</u> R. <u>W.</u>	B-10;B-11;C-10;C-11
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September 2, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and/or subsequent restoration.~~

C. (continued)

C-11

Fd. & accepted conc.mon. added  
cedar post w/loc. tag

7" W. Oak	S35°E	6.8
9" W. Oak	N55°E	33.1
4" R. Pine	S38°W	5.3

Fd. axle shaft S70°13'W 179.56

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 0 Established center of Sec. 30 at intersection of one-quarter lines.
- 1 Reestablished ¼ corner on line between sec. corners to E & W & at prorated distance to G.L.O. survey.
- 0 Reestablished ¼ corner per std. B.L.M. instructions. U.S.F.S. sq'd. post, at SW corner of R. Pine planting is 36' N and 55' E.
- 1 Found and accepted concrete monument per Sam Walker survey, dated 1949.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-10	B-11	C-10
Set 1½"x30" pipe & cedar post w/loc. tag	Set DNR mon. & ced. post	Set DNR mon. & cedar post
11" B. Oak N15°W 9.6	17" Cedar N70°E 62.7	6" B. Oak N60°W 8.8
11" W. Oak N80°E 19.2	23" W. Pine S30°E 37.2	5" Maple N25°W 23.1
	S'y edge Little Manistee River Due N 20'	4" R. Pine N40°E 45.1

SIGNED BY Carl F. Roser 9-15-76 DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

STRONACH TOWNSHIP  
MANISTEE COUNTY

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_