

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>21</u> N. R. <u>15</u> W.	H-12; I-12
2. PROPERTY CONTROLLING IN SECTION <u>33</u>	T. <u>21</u> N. R. <u>15</u> W.	14; 15
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 3, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~A. Description of original monument and accessories and for subsequent restoration:~~

C. (continued)

	15
Set 1"x2' pipe & ced. post w/loc. tag	
6" W. Pine	N75°E 19.4
Well Point	S60°E 14.41

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-12 Established center of Sec. 34 at intersection of one-quarter lines.
- I-12 Found U.S.F.S. concrete monument for ¼ corner common to Sec. 34 & 35.
- 14 Established corner per standard B.L.M. instructions.
- 15 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-12	I-12	14
Set 1½"x27" pipe & cedar post w/loc. tag	Fd. FS conc. mon. in road intersection	Set 1½"x24" pipe & cedar post w/loc. tag
4" W. Pine N60°W 49.0	Power Pole S50°E 54.54	3" Maple N70°W 4.8
8" W. Oak N80°E 8.1	9" R. Oak S60°W 57.26	7" W. Pine S87°W 42.4
	4"x4" post w/loc. tag N50°E 46.82	N-S random Due E 0.8
	9" Oak in clump of 3 S45°W 81.36	


SIGNED BY Carl F. Roser 9-15-76 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ STRONACH TOWNSHIP
MANISTEE COUNTY

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET