

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. _____	N. S., R. _____ E. W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>34</u> , T. <u>21</u> , R. <u>15</u> W. <u>13; 14; 15; 16</u>	N. S., R. _____ E. W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____ , T. _____	N. S., R. _____ E. W. _____	_____
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 3, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

~~Re = Description of original monument as shown on record = subject to restoration:~~

C. (continued)

16
 Set 1 1/4"x24" pipe & cedar post w/loc. tag
 5" W. Oak N15°W 6.0
 19" R. Pine Due W 36.8
 Fd. 3/4" pipe (probably Dodt) N65°W 2.30

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- 13 Recovered center of SE 1/4 Sec. 34 as conc. mon. per survey by R.L.S. Ken Ross.
 - 14 Recovered 5/8" rod by R.L.S. Ken Ross.
 - 15 Established W 1/16 on S line Sec. 34 equidistant & on line between S 1/4 & SW of Sec. 34.
 - 16 Established E 1/16 on S line Sec. 34 equidistant & on line between S 1/4 & SE of Sec. 34.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

13	14	15
Found & accepted Ross conc. mon. added ced. post w/loc. tag	Found 5/8" ref. rod Power Pole N85°E 59.06	Set 1 1/4"x34" pipe & cedar post w/loc. tag
7" Basswood S65°E 1.96	Red Pine S40°E 33.10	6" W. Oak N10°W 13.1
1" pipe S01°01'E 105.0	Conc. mon. & ced. post w/loc. tag N87°42'W 33.0	11" W. Oak N80°E 27.5
1/2" iron rod S87°42'E 192.9	Ctr. N-S gravel Road Due W 5.0	Fd. 1/2" pipe S47°W 41.51

SIGNED BY Carl F. Roser 9-15-76 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ STRONACH TOWNSHIP
 MANISTEE COUNTY