

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>21</u> ^{N.} <input checked="" type="radio"/> , R. <u>15</u> ^{W.} <input checked="" type="radio"/>	<u>H-11; I-11</u>
2. PROPERTY CONTROLLING IN SECTION <u>34</u>	T. <u>21</u> ^{N.} <input checked="" type="radio"/> , R. <u>15</u> ^{W.} <input checked="" type="radio"/>	<u>8</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} <input type="radio"/> , R. _____ ^{E.} <input type="radio"/> ^{S.} <input type="radio"/> , ^{W.} <input type="radio"/>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Carl F. Roser, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on November 4, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- H-11 Found spike & witness per survey of Sec. 34 by R.L.S. Ken Ross.
- I-11 Restored NE corner Sec. 34 from two County Road Commission witnesses.
- 8 Established corner per standard B.L.M. instructions.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11	I-11	8
Fd. cabin spk. in ctr. E-W rd. added 1½"x24" iron pin	Buried DNR monument	Set 1½"x36" pipe & cedar post w/loc. tag
4" W. Pine S40°E 54.04	12" Oak N55°E 66.38	7" W. Pine N10°E 71.5
6" W. Pine N25°E 40.02	15" Oak S83°E 41.75	14" B. Oak S80°W 19.1
16" B. Oak S40°W 55.34	7" W. Pine N65°W 39.07	
Set cedar post w/loc. tag	Set cedar post w/loc. tag	
Due S 33'	Due W 33'	

SIGNED BY Carl F. Roser 9-15-76 DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 12028


FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ STRONACH TOWNSHIP
MANISTEE COUNTY