

MAY 1 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Manistee (County) Located In: Corner Code #
1. Public Land Survey T 21N R 15W D-9
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

REGISTER'S OFFICE
MANISTEE COUNTY

96-186 at 1:20 pm
MAY 15 1996

Leborad Six

REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column D and row 9.

I, Richard Hays, in a field survey on April, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-9 QUARTER CORNER COMMON TO SECTIONS 20 & 29
1837:G.L.O. Set Post 1908:D. Skeels, Book B, Pg 250 1975:Roser #12028 L.C.R.C. 77-09
7" P. Pine N-10°-E 33 Lks(1) 10" J. Pine N-60°-W 31 Lks(3) Pd. Manchester Stone, Set DNR Monument
7" P. Pine S-86°-W 50 Lks(2) 10" J. Pine S-41°-W 30 Lks(4) 5" W. Pine S-45°-W 30.2'(5)
5" W. Pine S-80°-W 62.2'(6)
1929:W.D. Manchester 1974:Slawinski, Pd. Stone, No 10" B. Oak N-10°-E 32.9'(7)
Large Stone & Roots of both Witnesses. Cedar Post South 33.0'(8)

1990:Ross #17634, Act 132, L-2, Pg 576
Pd. DNR Monument, No Witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9 QUARTER CORNER COMMON TO SECTIONS 20 & 29
1996:Found D.N.R. Monument. Condition of Recorded Witnesses are
7" P. Pine N-10°-E 33 Lks(1) GONE
7" P. Pine S-86°-W 50 Lks(2) GONE
10" J. Pine N-60°-W 31 Lks(3) GONE
10" J. Pine S-41°-W 30 Lks(4) GONE
5" W. Pine S-45°-W 30.2' (5) GOOD
5" W. Pine S-80°-W 62.2' (6) GOOD
10" B. Oak N-10°-E 32.9' (7) GOOD
Cedar Post South 33.0' (8) GONE

Corner D-09 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: MAY 07 1996

Anthony M. Slawinski


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D-9 QUARTER CORNER COMMON TO SECTIONS 20 & 29

1996:Accepted D.N.R. Monument with cap stamped to identify corner and is accepted as the best available evidence of the position of the Original Corner.

8" W. Pine S-46°-W 30.05' (5)
11" W. Pine S-82°-W 62.67' (6)
7" W. Oak N-36°-W 31.90'
15" B. Oak N-10°-E 33.29' (7)
Ross Iron North 33.00'

Monument is 2' North of Centerline of Two Track

Signed by Richard Hays
Surveyor's Michigan License No. 25847



Date May 7, 1996