

MAY 16 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Table with columns: For corners in Manistee (County), Located In:, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Section.

REGISTER'S OFFICE
MANISTEE COUNTY
96-179 at 11:50AM
MAY 15 1996
Deborah Six
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. A dot is marked at row 12, column C.

1. Richard Hays in a field survey on April 19 96 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13 SOUTH QUARTER CORNER FOR SECTION 32
1837:G.L.O. Set Post 1971:Griffin #13504 L.C.R.C. 72-23 Did not find 1977:Roser #12028 L.C.R.C. 77-14
10" Y. Pine N-28 1/2'-W 184 Lks(1) Corner Reestablished from SE Cor of Sec 32 & N 1/4 Section Survey Fd. U.S.F.S. Mon.
10" Y. Pine S-64'-E 269 Lks(2) of Sec. 6 T20N-R15W-Witness #3 and found Witnesses #4-#7
4" W. Oak N-21'-E 78.82'(4)
1918:Theodore Norlin, Fd. Old Stake 4" W. Oak N-66'-E 54.14'(5)
N 1/4 Cor. Sec 6, T20N-R15W 5" W. Oak N-10'-E 69.49'(6)
Concrete Monument East 244.00'(3) 4"x7' Post North 33.11'(7)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 SOUTH QUARTER CORNER FOR SECTION 32
1996:Found U.S.F.S. Monument Broken and laying over on side. Condition of Recorded Witnesses are

10" Y. Pine N-28 1/2'-W 184 Lks(1)GONE
10" Y. Pine S-64'-E 269 Lks(2)GONE
N 1/4 Cor. Sec 6, T20N-R15W Concrete Monument East 244.00'(3)GOOD
4" W. Oak N-21'-E 78.82'(4)GOOD
4" W. Oak N-66'-E 54.14'(5)GOOD
5" W. Oak N-10'-E 69.49'(6)GOOD

Corner ... established by the Manistee County Peer Group according to the ... P.A. 045 of 1990, as amended, (being the ... Act, MCL 54.261 et seq.). Date of Peer Review MAY 07 1996
MAY 07 1996 Anthony M. Shambles


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 SOUTH QUARTER CORNER FOR SECTION 32
1996:Replace U.S.F.S. Monument with a Manistee County Monument with brass cap stamped to identify Corner and is accepted as a careful and faithful reestablishment

of the position of the Original Corner.

7" W. Oak N-46°-e 54.14'(5)
7" W. Oak N-21°-E 78.82'(4)
9" W. Oak N-10°-W 69.49'(6)
4"x7' Post North 33.11'(7)
Centerline of Road North 8.00'

Signed by Richard Hays
Surveyor's Michigan License No. 25847



Date May 7 1996