

MAY 18 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Manistee (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T	<u>21</u> N	<u>15</u> W	<u>E-9</u>
	T	_____	R	_____
	T	_____	R	_____
	T	_____	R	_____
2. Property Controlling in Section	S	_____	T	_____
	S	_____	T	_____
3. Miscellaneous Property in Section	S	_____	T	_____
	S	_____	T	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REGISTER'S OFFICE  
MANISTEE COUNTY  
#96-403 at 3:00 p.m.  
SEP 18 1996  
Person A. Pepera  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Richard Hays, in a field survey on April, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

**E-9 SECTION CORNER COMMON TO SECTIONS 20, 21, 28 & 29**

1837:G.L.O.	1908:D. Skeels, Old Corner,	1938:Lyons, U.S.P.S. Iron Bar(bent) NOTE:THIS INFORMATION IS MISLABELED ON THE GOVERNMENT CARD AND DOES NOT FIT ANY PHYSICAL EVIDENCE IN THE FIELD.
12" Y. Pine N-47 1/2°-E 83 Lks(1) No Witnesses		
22" W. Pine N-53 1/2°-W 33 Lks(2)		
1974:Slawinski #13597 Pd. 1/2" Iron Pd. Spike, Set 1-1/4"x22" Iron Pin	1975:Carl Roser #12028 L.C.R.C. 77-09	
4" J. Pine Southeast 62.22'(3)	5" J. Pine N-68°-W 64.02'(6)	14" W. Oak S-38°-W 133.32'
10" J. Pine Northeast 85.25'(4)	11" J. Pine N-33°-E 85.25'(7)	11" W. Oak S-47°-E 96.36'
5" J. Pine Northeast 64.07'(5)	10" J. Pine S-60°-E 62.20'(8)	7" U.S.P.S Post S-79°-W 0.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**E-9 SECTION CORNER COMMON TO SECTIONS 20, 21, 28 & 29**  
1996:Found 1-1/4"x22" Iron Pin set by Carl Roser. The condition of the Recorded Witnesses are as follows:

12" Y. Pine N-47 1/2°-E 83 Lks(1) GONE
22" W. Pine N-53 1/2°-W 33 Lks(2) GONE
4" J. Pine Southeast 62.22'(3)(8) GOOD
10" J. Pine Northeast 85.25'(4)(7) GOOD
5" J. Pine Northeast 64.07'(5)(6) GOOD

Corner E-09 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et. seq.). Date of Peer Review: SEP 17 1996  
Anthony M. Slawinski

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**E-9 SECTION CORNER COMMON TO SECTIONS 20, 21, 28 & 29**  
1996:Replace Found 1-1/4"x22" Iron Pin with Manistee County Monument with cap stamped to identify Corner and in Monument Box and is accepted as a the best available evidence of the position of the Original Corner.

8" J. Pine N-66°-W 64.02'(6)	13" J. Pine S-60°-E 62.32'(8)
15" J. Pine N-32°-E 85.25'(7)	14" B. Oak S-44°-W 50.93'
13" R. Pine S-52°-E 65.60'	

Signed by Richard Hays  
Surveyor's Michigan License No. 25847



Date: July 1 1996