

OCT 31 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Manistee
(County)

Located In:

Corner Code #

1. Public Land Survey

T 21N R 15W

J - 3

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

4. Lot No. Recorded Plat

5. Private Claims

REGISTER'S OFFICE
MANISTEE COUNTY

#94-371 AT 2:45 p.m.
AUG 16 1994

Army A. Peters
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Kenneth L. Ross in a field survey on July 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-3 One-quarter corner common to sections 2 & 11, T21N, R15W

1837, John Brink D.S., GLO page 39
Set wood post

- 1. W. Pine 16" N41E 57 lks
- 2. Y. Pine 9" S45W 8 lks
- 5/1/81 Manistee County Road Commission
- Set Concrete Monument
- 3. Oak 24" S50E 75.81'

- 4. J. Pine 10" S25E 80.50'
- 5. J. Pine 10" S30W 51.50'
- 6. Oak 10" S50W 60.00'
- 7. Oak 12" Due South 59.92'

- 1986 K. Ross # 86 - 440
- Replaced concrete monument with 5"x36" brass capped monument USFS
- 8. R. Pine 12" S24E 80.38'
- 9. R. Pine 10" S40W 71.66'
- 10. W. Pine N02E 125.32'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-3 One-quarter corner common to sections 2 & 11, T21N, R15W

On 7/21/94 found 5"x36" brass capped concrete monument USFS & and accepted it as a substantial marker for corner.

Condition of record witnesses are;

- 1. gone 2. gone 3. found in good condition 4. found in good condition 5. found in good condition 6. found in good condition 7. found in good condition 8. same as 4
- 9. found in good condition 10. found in good condition

Corner J-3 ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act, MCL 54.261 et seq.). Date of Peer Review: Aug 1, 1994

*Barry J. J...
ACTING CHAIRMAN*


APPROVED AUG 1 1994

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3 One-quarter corner common to sections 2 & 11, T21N, R15W

Accepted 5"x36" brass capped concrete monument as a careful and faithful reestablishment of the original corner.

- (OBT 6) Red Oak 9" S50W 60.20 ft. (16d nail with shinner)
- (OBT 8) Red Pine 14" S24E 80.38 ft. (60d nail in SW side)
- (OBT 9) Red Pine 11" S40W 71.66 ft. (60d nail in SE side)
- (OBT 10) White Pine 9" S02E 125.32 ft. (60d nail in East side)



Signed by Kenneth L. Ross

Date Aug. 1, 1994

Surveyor's Michigan License No. 17634

