

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in \_\_\_\_\_

|                                       |  |                                       |
|---------------------------------------|--|---------------------------------------|
| <u>Manistee</u><br>(County)           | Located In:  | Corner Code #                         |
| 1. Public Land Survey                 | T 21 <sup>N</sup> R 15 <sup>W</sup><br>T 21 <sup>N</sup> R 15 <sup>W</sup><br>T 21 <sup>N</sup> R 14 <sup>W</sup><br>T _____ R _____ | M-6 E. 1/4 Sec. 13 ✓<br>M-6i<br>A O G |
| 2. Property Controlling in Section    | S _____ T _____ R _____<br>S _____ T _____ R _____   | _____                                 |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____<br>S _____ T _____ R _____   | _____                                 |
| 4. Lot No. _____, Recorded Plat _____ |  |                                       |
| 5. Private Claims _____               |  |                                       |

**REGISTER'S OFFICE**  
**MANISTEE COUNTY**  
 98.380 at 11:05am  
**SEP 17 1998**  
*Deborah Dix*  
**REGISTER OF DEEDS**

Register of Deeds Stamp & File Number

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 1  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Bruce J. Jenema, in a field survey on April 27, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- |  |  |
|--|--|
| M-6 1836, J. Brink, G.L.O.<br>Intersect line of 7,000 acre reserve<br>and set 1/4 post<br>(1) Y. Pine 14° S67°W 35 lk. (23.1')<br>(2) Beech 10° N68 1/2°W 55 lk. (36.3') | 1980, K. Ross<br>Set 1/2" x 24" iron & cap #17634<br>(4) Post West 1.1'<br>(5) R. Oak 10° S40°W 40.3'<br>(6) R. Oak 10° N40°W 43.31'<br>(7) R. Oak 8° N78°E 22.46' |
| 1907, J.H.M.<br>(3) W. Pine Stump 12° N28°E 35 lk. (23.1')   | 1993, J. Ray<br>Fd. (4) (5) (6) (7)  |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

On April 27, 1998 I found a 1/2" x 24" iron bar with cap #17634.  
 Note: Indian reserve corner and the E 1/4 corner of section 13 are one in the same.  
 No conflicting evidence of other corners exist.  
 Condition of accessories:

- (1) (2) (3) - now extinct  
 (4) (5) (6) (7) - fd. in good shape

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

On May 5, 1998 I placed a standard Manistee County Monument in the exact position of the above 1/2" x 24" iron bar and is accepted as the best available evidence of the position of the original corner and witnessed by:


- (4) Post West 1.1'  
 (5) R. Oak 10° S40°W spike S. side  
 (6) R. Oak 10° N40°W 43.31' spike N. side  
 (7) R. Oak 8° N78°E 22.46' spike N. side  
 (8) Oak 8° N90°W 12.90' 60-D N. side

Corner M - O G ratified by the Manistee County Peer Group according to the county plan adopted pursuant to P.A. 345 of 1990, as amended, (being the State Survey and Remonument Act MCL 54.261 et. seq.). Date of Peer Review: Anthony M. Hawkins

**AUG 04 1998**

Signed by Bruce J. Jenema  
 Surveyor's Michigan License No. 25850

Date 08-04-98



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 28, 19  
 REVISED MAY 14, 19  
 REVISED JAN., 1983  
 REVISED OCT., 1996